


For Reference

NOT TO BE TAKEN FROM THIS ROOM

Ex LIBRIS
UNIVERSITATIS
ALBERTAENSIS





Digitized by the Internet Archive
in 2022 with funding from
University of Alberta Library

<https://archive.org/details/Baird1978>

THE UNIVERSITY OF ALBERTA

WATERFLOOD BEHAVIOR OF VISCOUS OILS

by



HENRY J. BAIRD

A THESIS

SUBMITTED TO THE FACULTY OF GRADUATE STUDIES AND RESEARCH
IN PARTIAL FULFILMENT OF THE REQUIREMENTS FOR THE DEGREE
OF MASTER OF SCIENCE
IN
PETROLEUM ENGINEERING

DEPARTMENT OF MINERAL ENGINEERING

EDMONTON, ALBERTA

FALL, 1978

ABSTRACT

Waterflooding tests were carried out on unconsolidated sands packed in stainless steel coreholders to investigate the relationship between oil recovery and a scaling number which is the ratio of viscous to capillary forces. The cores were approximately 4 ft. (1.34 m) long and were of two diameters; 4 in. (10.16 cm) and 2 in. (5.08 cm). The permeability of the cores varied between 8 and 16 darcies and the porosity was constant at about 36%. A completely new sandpack was used for each waterflood run performed.

The main parameter studied was the rate of injection which was varied between 2.5 and 800 cc/hr. Two oils were used; the first a Dow Corning 200 fluid (500 c.s.) and the second a Wainwright crude oil (1080 c.s.). All runs were performed in the presence of an initial water saturation in the core.

Both oils exhibited rate sensitive breakthrough recoveries. With the Dow Corning fluid the recovery showed a decrease in breakthrough recovery as injection rate was increased whereas with the Wainwright crude oil breakthrough recovery increased with increasing injection rate. Completely different mechanisms were postulated to explain the seemingly contradictory results.

A region of non-Darcy flow was found to exist at high displacement rates but could not be used to explain the trend in observed breakthrough recoveries. Fingering in the core at the flood front would explain the decrease in breakthrough recovery with increasing rate of injection observed in the tests with Dow Corning fluid. For the Wainwright crude oil, water-in-oil emulsions were formed in-situ and this emulsification provided a five-fold increase in breakthrough recovery from very low rates to very high rates.

Mixing associated with increasing rates produced the emulsions which resulted in the increase in recovery; however, these rates were very much higher than field conditions would allow.

Emulsion stability appeared to correlate with the amount of recovery and this stability appears to be related to either the absolute permeability or to the amount of initial water present in the core.

ACKNOWLEDGEMENT

The author gratefully appreciates the academic guidance and encouragement of Dr. D. L. Flock during his supervision of this investigation. Acknowledgement is also made to Dr. R. G. Bentsen whose suggestions and comments were greatly appreciated. Financial aid from the Alberta Oil Sand Technology and Research Authority and also the Petroleum Aid to Education Fund is gratefully acknowledged.

TABLE OF CONTENTS

| CHAPTER | PAGE |
|--|------|
| I INTRODUCTION | 1 |
| II BACKGROUND | 3 |
| III EXPERIMENTAL EQUIPMENT AND MATERIALS | 10 |
| A. Equipment | 10 |
| B. Sand | 13 |
| C. Fluids | 14 |
| IV EXPERIMENTAL PROCEDURE | 15 |
| A. Packing of the Cores | 15 |
| B. Saturating the Packed Core | 16 |
| C. Displacement Tests | 18 |
| V DISCUSSION OF RESULTS | 19 |
| A. Sandpack Properties | 19 |
| B. Fluid Properties | 21 |
| C. Displacement Tests With Dow Corning | 22 |
| D. Darcy Law Cross-Plots | 33 |
| E. Relative Permeability Calculations. | 37 |
| F. Calculation of the Chouke Constant. | 37 |
| G. Calculation Using van Meurs and van der Poel | 38 |
| H. Displacement Tests With Wainwright Crude Oil | 45 |

TABLE OF CONTENTS (Continued)

| CHAPTER | PAGE |
|---|------|
| VI OBSERVATIONS AND CONCLUSIONS | 54 |
| VII RECOMMENDATIONS | 56 |
| NOMENCLATURE | 58 |
| REFERENCES | 61 |
| APPENDIX A - FLUID PROPERTIES | 64 |
| APPENDIX B - RECOVERY HISTORY CURVES | 70 |
| APPENDIX C - RELATIVE PERMEABILITY CALCULATIONS | 96 |
| APPENDIX D - TABULATED EXPERIMENTAL DATA | 111 |

LIST OF TABLES

| TABLE | PAGE |
|--|------|
| 1. Core Properties | 20 |
| 2. Displacement Test Summary | 23 |
| 3. Calculation of C | 40 |
| 4. van Meurs Recovery Calculations | 40 |

LIST OF FIGURES

| FIGURE | PAGE |
|---|------|
| 1. Schematic Flow Diagram of Displacement Apparatus | 12 |
| 2. Recovery vs. I for Dow Corning Fluid | 26 |
| 3. Displacement of Oil by Water (water-wet) | 29 |
| 4. Displacement of Oil by Water (oil-wet) | 29 |
| 5. Recovery vs. I (WOR = 6 & 20) | 32 |
| 6. Darcy Law Crossplot (2 inch core) | 34 |
| 7. Darcy Law Crossplot (4 inch core) | 35 |
| 8. Idealized Picture of Water Fingers | 39 |
| 9. Comparison of Experimental Recoveries with van Meurs Calculated Recoveries | 44 |
| 10. Recovery vs. I for Wainwright Crude Oil | 46 |
| 11. Water-in-Oil Emulsion (magnified 400X) | 48 |
| 12. Water-in-Oil Emulsion (magnified 650X) | 48 |
| 13. Darcy Law Crossplot (Wainwright Crude Oil) | 52 |

I. INTRODUCTION

Waterflooding is the oldest of the enhanced recovery methods having been discovered by accident in 1865. It is still the most important of the secondary recovery methods in terms of oil produced and in the Province of Alberta over 80% of the oil recovered by enhanced recovery methods is by waterflood. Because of its popularity a colossal amount of literature is available on the subject. Many contradictions exist in this literature.

One of the most controversial parameters in a waterflood design is the rate of injection. Many researchers^{3,15,18,20} report increasing breakthrough recovery with increasing rate, while others report stabilized recovery^{8,16} and others^{5,9,10,13,23} report decreasing recoveries with increasing rate of injection. The phenomenon of viscous fingering has been investigated by many researchers^{4,5,7,10,13,21,23}, including some from the Department of Mineral Engineering at the University of Alberta. Low viscosity to medium viscosity oils have been used in these studies. As production of heavy crude oil becomes more economical high viscosity crudes should be investigated with particular reference to waterflood behavior. Since the economics of waterflooding has been proven in many conventional light oil reservoirs it may well be applied with some

success to heavier oil reservoirs.

The aim of this work was to examine the behavior of viscous oil (i.e. Wainwright crude oil - 1000 c.s.). Also an attempt was made to obtain laboratory data free of changing initial conditions such as rising initial water saturations from run to run.

II. BACKGROUND

Engelberts and Klinkenberg¹⁰ coined the term "viscous fingering" from observations of their experimental work in 1951. They visually observed gross water channeling at high water injection rates in water-wet systems leading to severe decreases in breakthrough recoveries. The fingers in their system were attributed to instabilities developing in the transition zone separating the injection water from the undisplaced oil. They were able to correlate their results by the use of the scaling group "I" which is a ratio of viscous to capillary forces in the core.

$$I = \frac{LV\mu_w}{\sigma\sqrt{K}} \quad (1)$$

I = ratio of viscous to capillary forces
(dimensionless)

L = length of sand pack (cm)

μ_w = viscosity of water in system (cp)

σ = interfacial tension (dynes/cm)

K = absolute permeability of sand pack (cm²)

V = velocity of the front (cm/s)

Rapoport and Leas¹⁸ and Kyte and Rapoport¹⁴ show that the scaling group "I" controls the length of the capillary transition zone in the system. As the value of the scaling group decreases this transition zone increases. The

transition zone referred to here is the frontal region between the initial water saturation and the flood front saturation (Sw_f). As the scaling group increases the flood becomes stabilized (i.e. the capillary transition zone does not change with time) and the recovery becomes insensitive to further rate increases. At highly unfavourable viscosity ratios they did observe a decrease in recovery as rate was increased but they attributed this to an inlet end effect.

Geertsma et al.¹² examined all the variables relevant to waterflooding and developed a more general dimensionless scaling group which they called the Leverett number (L_t). L_t is the ratio of capillary to viscous forces in the core.

$$L_t = \frac{\sigma \cos \theta \sqrt{K\phi}}{\mu_w VL} \quad (2)$$

where:

θ = wetting angle of fluid interface
(dimensionless)

ϕ = porosity (dimensionless)

The scaling group "I" is a simplification of this group and may be used if the wettability conditions and porosity are held constant.

In 1957 van Meurs and van der Poel²¹, using an idealized representation of viscous fingers, developed a mathematical description of waterflooding involving viscous

fingering. Wiborg²³ presented this theory in detail in his thesis in an attempt to predict the results of his experimental studies.

Chouke et al.⁴ in 1958 derived a theoretical description for viscous fingering by formulating an equation for the peak to peak separation of the fingers.

$$\lambda_m = C \left[\frac{\sigma K}{V(\mu_o - \mu_w)} \right]^{1/2} \quad (3)$$

λ_m = the average wave length (peak to peak) (cm)

K = absolute permeability (cm²)

V = superficial velocity (cm/sec)

σ = interfacial tension (dynes/cm)

μ_o, μ_w = oil and water viscosity (poise)

C = CHOUKE constant (dimensionless)
(different for each system)

The constant C was introduced to allow for the fact that the effective interfacial tension in a porous medium containing connate water will be somewhat greater than that measured in the laboratory on a planar surface. They assumed that this effective interfacial tension would be directly proportional to the measured interfacial tension, hence the constant C .

They also related this average wavelength to a critical wavelength which is the smallest wavelength possible at the onset of fingering.

$$\lambda_{cr} = \lambda_m / \sqrt{3} \quad (4)$$

where: λ_{cr} = critical wavelength

At the onset of fingering the critical wavelength must equal the model width, D, or $\lambda_{cr}/D = 1$. This critical wavelength for the system adds a third requirement for instability because capillary forces have been considered in Chouke's analysis. The three conditions necessary for instability are:

1. A velocity greater than some critical velocity defined for the system.
2. An adverse mobility ratio.
3. The system must contain modes of wavelengths greater than the critical wavelength of the system.

By using the fact that at the onset of fingering the critical wavelength must be the same size as the model width an expression for C for the particular system may be obtained.

$$C = \left[\frac{3 V (\mu_o - \mu_w) D^2}{\sigma K} \right]^{1/2} \quad (5)$$

By solving Equation (1) for σ and substituting into Equation (5), we obtain C in terms of the scaling group "I".

$$C = \left[\frac{3 \left(1 - \frac{\mu_o}{\mu_w} \right) D^2}{L\sqrt{K}} \right]^{\frac{1}{2}} \quad (6)$$

Chouke⁴ also states that additional scaling is needed if viscous fingering is present in the system and suggests that the group $[\lambda_m/D]^2$ be the same in the model and the prototype. However, he identifies three cases found in laboratory floods and states that for two of the cases the additional scaling rule may be dropped.

Case 1) $\lambda_m/D \ll 1$ here a large number of fingers are present and Chouke suggests that production is independent of rate.

Case 2) $\lambda_m/D \gg 1$ here the peak to peak distance is larger than the width of the model and the behavior is then like that of a stable displacement.

Case 3) $\lambda_m/D \approx 1$ here the finger spacing is approximately equal to the canal width and the production behavior could be affected. When this condition is met the additional scaling parameter $[\lambda_m/D]^2$ is needed and should be the same in the model and the prototype.

Kloepfer¹³ in 1975, observed the effect of rate on the displacement efficiency at favourable and unfavourable

Viscosity ratios. He found no decrease in breakthrough recovery as the rate was increased when the viscosity of the displacing phase was greater than that of the displaced phase. He did notice a decrease in recovery at unfavourable viscosity ratios as the rate of injection was increased.

There were problems in interpreting the data for the viscosity ratio (μ_o/μ_w) of 6.4 since the wettability of the sand pack appeared to be changing as the flood series progressed. To prepare the core for a new flood a displacement, with oil, was conducted until initial conditions were established without cleaning between the runs. According to Kloepfer¹³ this substantial period of time from the start to the finish of a series may have allowed polar type components in the crude oil to adsorb on the sand surface. A decrease in breakthrough recovery was noted in the runs that were considered to be water-wet and no decrease was noted in the runs considered to be neutral or oil-wet.

Wiborg²³, in 1976, studied the effect of injection rate at more adverse viscosity ratios. He used three oils with viscosities varying from 14 to 110 centipoise. The results indicated a decrease in breakthrough recovery as the rate of injection was increased for all three oils. Wiborg²³ attributed this decrease in recovery to fingering within the core. With one of his oils the recovery increased again as the rate of injection was increased to

very high values. For this oil Wiborg²³ observed water-in-oil emulsions being produced from the core at these very high rates.

A major problem encountered by Wiborg²³ was a continually rising initial water saturation. His initial water saturations varied from 10-15% at the start to 25-30% at the end of his series of runs for two of his oils. For his third oil, a Dow Corning fluid, the initial water saturation was relatively constant from run to run. Wiborg²³ noted that when resaturating with this Dow Corning fluid he would have to stop injection when the initial water saturation was in the proper range to avoid a decreasing initial water saturation from run to run. This might be explained by a change in wetting characteristics within the core. The core pack was changing from water-wet to oil-wet. Oil-wet systems typically exhibit lower connate water saturations than similar systems that are water-wet.

III. EXPERIMENTAL EQUIPMENT AND MATERIALS

A. EQUIPMENT

The coreholders used for this set of displacement tests were made of stainless steel and of the same design as those used by Wiborg²³. The majority of runs were performed using the 2 inch inside diameter coreholder and considerably fewer runs were made using a 4 inch inside diameter coreholder. Both coreholders yielded sand packs of approximately 107 cm in length depending on the amount of sand added in the packing process. The endcaps and coreholders are described in detail by Wiborg²³ and the design specifications are also contained in his thesis.

Whereas Wiborg²³ used only a 200 mesh screen to prevent the sand from plugging the radial and concentric grooves in the endcap face, this set of experiments was performed using a 400 mesh screen clamped to the endcap and a double-200 mesh screen was also placed between the 400 mesh screen and the sand. It was thought that this would help to allow the injection water to reach the sand face more uniformly and make the physical inlet end effect very small. The double-200 mesh screen acts as an additional spreader plate to aid the grooves in the injection head face.

A schematic diagram of the displacement equipment is shown in Figure 1. Mercury was injected into the fluid bombs by a constant rate Ruska pump which displaced fluid out of the bomb and into the core. This procedure was followed so that the pump did not have to be cleaned with every change from oil to water or water to oil; the bombs could simply be drained and refilled. Mercury was the only substance in contact with the pump. All fluid lines were made of high pressure stainless steel tubing.

When a packed core was ready to be waterflooded it was placed on an automatic rotating device which in the case of the 2 inch diameter cores rotated the core one revolution per hour. The purpose of the rotator was to eliminate the effect of gravity in the core and try and prevent a water tongue from forming along the bottom of the coreholder. This rotating of the core necessitated the introduction of the high pressure swivel head at the upstream end of the core.

The produced fluids simply dropped from the downstream end of the core into 50 ml graduated centrifuge tubes. The centrifuge tubes were in a circular holder which held 24 tubes and this holder was connected to a motor and a timing device made it possible to select a time interval for each tube. When the timer was used the collector would automatically switch to the next tube when the set time had expired. For example, if a time of 5




FIGURE 1: SCHEMATIC OF DISPLACEMENT EQUIPMENT

minutes was chosen, an empty tube would be rotated into place under the end of the core every 5 minutes. A small centrifuge was used to centrifuge all production to ensure complete separation of the phases after varsol had been added.

A Heise gauge or mercury manometer, depending upon the magnitude of the pressure drop expected, was used to obtain the pressure drop across the core.

The viscosity profiles shown in Appendix A were obtained using Cannon-Fenske viscometers in a liquid temperature bath to give the range of temperatures needed. The viscosity of water was taken from Perry and Chilton¹⁷.

Interfacial tensions were all measured with a Du Nouy tensiometer and the values reported are actually arithmetic averages of a series of tests for each pair of fluids.

B. SAND

The sand used for all runs was Fisher Scientific silica (S-151). This sand had a grain size range of 80-120 mesh and no further sieving was performed. The sand was used as purchased, except for heating it to 1000°F to rid it of any organics that may have been present on the surface of the sand grains.

C. FLUIDS

Distilled water was used as connate water and displacing water in all experimental runs.

Two oils were chosen for this group of tests. The first, a Dow Corning 200 fluid, had a viscosity of 500 c.s. at 70°F (21.1°C). This is a silicone base oil which exhibits a rather flat viscosity-temperature profile, a low surface tension and a low vapor pressure. In short the properties of the fluid are quite stable and will not change greatly from run to run. However, from personal communication with Dr. Bentsen, some experimental measurements indicate that Dow Corning fluids deteriorate with age and possibly are dilatant. As a consequence these fluids may exhibit dilatant rather than Newtonian behavior.

The second oil chosen for this series was a Wainwright crude oil which contained about 6% water "as received" from the field. By applying heat and a vacuum at the same time the water was removed from the oil. The tests were run using this water free crude, which had a viscosity of 1080 c.s. at 70°F.

A summary of some fluid properties is available in Appendix A.

IV. EXPERIMENTAL PROCEDURE

A. PACKING OF THE CORES

The silica sand used for all runs was placed in an oven at 1000°F (538°C) for a minimum of 48 hours to burn off any organics that may have been on the sand grain surfaces. Imbibition tests carried out by Wiborg²³ indicate that this procedure makes this type of sand water-wet. When the sand had been "fired" in the above manner it was then ready to be packed into a core holder. One endcap was installed on the coreholder with the screens in place and it was then strapped to a bench, capped end down, after making note of the end cap length and volume. Mechanical vibrators operated by compressed air were affixed to the vertical core holder. Sand was added to the coreholder and the weight of any sand added was recorded. The grain volume could be estimated from its weight knowing the density of silica sand as 2.65 gm/cc. The pore volume was then calculated. The vibrators were left on at night (periods of 8-10 hours) until no more subsidence took place. This usually took 3-4 nights with the sand level being "topped up" each day. Blows with a rubber hammer also helped settle the sand. The upper endcap was installed with the screens and then the overall length of the coreholder was established, including the endcaps. The total

length minus the two endcap lengths yielded the sandpack length.

B. SATURATING THE PACKED CORE

The packed core was then attached to a vacuum pump and the core evacuated until the absolute pressure within the coreholder was 1-2 mm of mercury. The core was then placed in a vertical position and saturated with deaerated distilled water. The water was deaerated beforehand by drawing a vacuum on the water for 2-3 hours. The vertical position of the core is important for the simple reason that if any vapor does come off this water as it is introduced to the evacuated core it will be easier to extract out of the system in this position. Also no air will be trapped in the upper section of the core as could happen when the cores were saturated in the horizontal position.

When pressure started to build in the system the outlet valve was opened slightly to allow water to pass through into a graduated cylinder. This outlet valve was controlled so that a pressure of 60-70 psig was maintained on the system until at least one pore volume was flowed through. It was hoped that this procedure would put any vapor back into solution or at least make vapor bubbles, if any, in the core small enough to be displaced out of the system. The resulting core would be completely liquid

filled. The pump reading gave the total amount injected and the ejected fluid was measured, with the difference being the pore volume after allowing for the volume of the endcaps and fittings. These pore volumes, from the material balance when compared to the pore volumes established by using the weight and density of the sand, were consistently within 2% of each other.

Water was flowed through the core and the pressure drops were noted for a number of different rates and these were used to calculate an absolute permeability for the sandpack. A complete table of sandpack properties can be found in the next chapter. The reported permeability is the arithmetic average of a number of tests conducted on each core.

Oil was forced downward through the core displacing water out of the lower end. A volumetric balance was kept on the oil and water ejected and the respective initial saturations could then be calculated. The oil injection rate into the 2 inch cores, for the Dow Corning fluid, was 100 cc/hr. For the Wainwright crude oil injection was maintained at 80 cc/hr because of its greater viscosity. To account for a change in diameter the injection rate into the 4-inch core was 400 cc/hr. In the case of the smaller diameter cores approximately 1000 cc's of oil were injected. It was found that very little water was produced after the

oil broke through at the lower end of the core. The pressure drop across the core was also noted at this point so that an effective permeability to oil at initial water saturation could be calculated.

C. DISPLACEMENT TESTS

The core was now at initial conditions and ready for a waterflood to begin. The coreholder was placed on the automatic rotating device which was in a horizontal position for this set of experiments. The automatic collection device containing the centrifuge tubes was placed in position at the outlet end of the core and the pressure gauge was connected in at the upstream end of the core. The selected injection rate was obtained by choosing the correct gear ratios on the Ruska pump, and the flood was started. At convenient intervals, the volumes of produced oil and water were recorded, as well as the pressure drop, the amount injected and the time. The flood was continued usually until about 3 or 4 pore volumes had been injected. The runs were continued until very little more oil was produced and this point was then used to obtain K_{rw} at So_r .

When the run had been completed the coreholder was completely cleaned and washed and then repacked with new sand and the procedure repeated.

V. DISCUSSION OF RESULTS

A. SANDPACK PROPERTIES

A completely new sandpack was packed for each experimental run and the sand was not reused. This procedure should result in a more uniform wettability for the system and provide support for the fact that decreases in recovery with rate are simply not wettability changes. By packing a new core for each run much more time was consumed per run than during a simple resaturation procedure. However, if the core properties can be reproduced within reason, the results should be able to be interpreted with much more confidence. Table 1 lists the sandpack properties from run to run for the entire set. A "200" series was completed using two inch O.D. coreholders with slightly different I.D.'s as can be noted from the cross-sectional areas and a "400" series consisting of four tests was carried out on a four inch O.D. coreholder. The sandpack lengths are very uniform averaging 107.47 cm and these variations in length are caused by a slightly different amount of sand being added in the packing process from run to run. The porosity was very uniform as well, averaging 36.4%. The porosity of run 221 was a full 2% above this average. This run will be discussed later since it also exhibited an extremely low initial water saturation.

TABLE 1
CORE PROPERTIES

Sand - Fisher Scientific Silica (S-151)

80-120 mesh

- completely new sandpack for each run.

| Run # | Cross Sectional Area (cm ²) | Sandpack Length (cm) | Porosity (%) | Absolute Permeability (Darcies) |
|-------|--|----------------------------|-----------------|---------------------------------------|
| 201 | 19.32 | 107.15 | 36.5 | 15.40 |
| 202 | 19.32 | 107.95 | 36.9 | 17.34 |
| 203 | 19.32 | 108.61 | 36.7 | 16.39 |
| 204 | 19.32 | 107.73 | 37.2 | 13.75 |
| 205 | 19.32 | 107.75 | 36.0 | 8.43 |
| 206 | 19.01 | 107.31 | 36.1 | 7.56 |
| 207 | 19.32 | 107.72 | 36.8 | 8.54 |
| 208 | 19.32 | 106.92 | 38.0 | 16.72 |
| 209 | 19.01 | 107.81 | 35.5 | 8.66 |
| 210 | 19.32 | 107.04 | 36.0 | 12.45 |
| 211 | 18.93 | 107.19 | 36.5 | 12.64 |
| 212 | 18.93 | 108.12 | 36.3 | 12.00 |
| 213 | 19.01 | 107.02 | 35.2 | 10.34 |
| 214 | 19.32 | 107.82 | 36.2 | 8.56 |
| 215 | 19.32 | 107.50 | 35.5 | 8.33 |
| 216 | 19.01 | 106.52 | 35.2 | 8.17 |
| 217 | 19.32 | 107.25 | 36.0 | 9.42 |
| 218 | 18.93 | 108.02 | 35.5 | 9.66 |
| 219 | 19.32 | 107.37 | 35.7 | 11.43 |
| 220 | 19.32 | 107.21 | 37.0 | 12.52 |
| 221 | 18.93 | 107.76 | 38.4 | 15.09 |
| 401 | 74.36 | 107.42 | 37.0 | 16.46 |
| 402 | 74.36 | 107.34 | 37.1 | 18.28 |
| 403 | 74.36 | 107.01 | 37.4 | 11.33 |
| 404 | 74.36 | 107.17 | 36.2 | 10.39 |

There was much more scatter in the permeability from run to run as can be seen in Table 1. It was felt that these changes in permeability were due to slightly different average grain sizes in the different shipments of sand and since the sand was used just as it was supplied these grain size inconsistencies appeared to have affected the sandpacks from run to run. It is recommended that in the future, shipments of sand be sieved to a narrower grain size range before being used in displacement experiments to try and obtain a more reproducible permeability.

The dimensionless scaling coefficient that was used in this work to scale the results contains the permeability as a parameter and therefore these changes should not affect the interpretation of results unless a change of displacement mechanism takes place due to this change in permeability.

B. FLUID PROPERTIES

The fluid properties for the Dow Corning 200 experiments (runs 201-209 plus 401-404) were very consistent and the viscosity can be considered to be constant for the entire set of experiments. A temperature fluctuation of a few degrees made some difference in the Wainwright crude oil viscosity as can be seen from the properties listed in

Table 2. However, these fluctuations in viscosity do not appear to be great enough to have affected the displacement tests significantly if runs 215 and 216 are examined (see Table 2). These two sandpacks exhibit very close to the same porosity and permeability and the difference in displacement rates is not great (100 cc/hr and 80 cc/hr, respectively). However, the difference in oil viscosities between the two runs is close to the maximum variation for the entire series (821 cp and 1028 cp, respectively) yet the recovery is identical at breakthrough being 23.8% I.O.I.P.

C. DISPLACEMENT TESTS WITH DOW CORNING

A summary of the displacement test data appears in Table 2. Individual recovery curves for each run can be found in Appendix B and tabulated recovery data for each run can be found in Appendix D.

From Table 2, the water saturations for the Dow Corning runs can be seen to be relatively constant, ranging from 9.7% to 12.5% over the series and averaging just over 11%. The problem that Wiborg²³ had with rising water saturations does not occur in these tests. Two possible reasons for the elimination of this problem are:

1. With a new sandpack for each run any material balance errors are not carried forward to the next run.

TABLE 2.
DISPLACEMENT TEST SUMMARY

| Run | Oil | Oil Viscosity | | Swi (%) | Koi (Darcy) | Q (cc/hr) | V x 10 ³ (cm/sec) | RECOVERY (%IOIP) | | RECOVERY (%PV) | | I x 10 ³ | | |
|-----|------------------|---------------|---------------|---------|-------------|-----------|------------------------------|------------------|-------|----------------|--------|---------------------|-------|---------|
| | | (cp) | μ_o/μ_w | | | | | B.T. | WOR=6 | WOR=20 | WOR=20 | | | |
| 201 | ← | 533 | 549.6 | 9.80 | 13.35 | 2.5 | 0.036 | 27.22 | 34.00 | 40.20 | 24.55 | 30.67 | 36.26 | 2.84 |
| 202 | | 533 | 541.1 | 11.26 | 13.55 | 10.0 | 0.144 | 24.41 | 28.9 | 35.7 | 21.45 | 25.40 | 31.37 | 11.02 |
| 203 | | 533 | 541.1 | 11.45 | 14.31 | 160.0 | 2.300 | 19.74 | 29.4 | 37.3 | 17.43 | 26.03 | 33.03 | 182.40 |
| 204 | | 533 | 541.1 | 12.50 | 12.12 | 300.0 | 4.313 | 16.98 | 28.0 | 35.1 | 14.86 | 24.51 | 30.72 | 373.68 |
| 205 | 200 | 533 | 549.6 | 11.44 | 7.30 | 800.0 | 11.502 | 16.28 | 27.1 | 36.7 | 14.42 | 24.00 | 32.50 | 1261.80 |
| 206 | | 533 | 533.0 | 10.58 | 6.66 | 20.0 | 0.292 | 25.87 | 26.0 | 40.9 | 23.13 | 23.45 | 36.57 | 33.73 |
| 207 | | 533 | 541.1 | 11.86 | 8.18 | 560.0 | 8.052 | 16.17 | 29.5 | 37.1 | 14.25 | 26.0 | 32.70 | 877.60 |
| 208 | | 533 | 541.1 | 12.46 | 14.95 | 50.0 | 0.719 | 20.90 | 31.4 | 39.3 | 18.30 | 27.49 | 34.40 | 55.59 |
| 209 | DOW CORNING | 533 | 549.6 | 9.70 | 8.18 | 15.0 | 0.219 | 23.77 | 29.9 | 40.2 | 21.47 | 27.00 | 36.31 | 23.74 |
| 401 | | 533 | 549.6 | 10.20 | 15.00 | 10.0 | 0.037 | 16.07 | 26.7 | 32.6 | 14.43 | 23.98 | 29.28 | 2.925 |
| 402 | | 533 | 549.6 | 10.80 | 15.73 | 40.0 | 0.149 | 25.11 | 28.9 | 33.6 | 22.31 | 25.68 | 29.86 | 11.196 |
| 403 | | 533 | 533.0 | 11.73 | 10.09 | 600.0 | 2.241 | 15.2 | 28.3 | 36.5 | 13.42 | 24.98 | 32.22 | 212.66 |
| 404 | → | 533 | 549.6 | 10.34 | 9.89 | 1120.0 | 4.184 | 15.1 | 29.9 | 36.7 | 13.33 | 26.39 | 32.40 | 415.16 |
| 210 | | 947 | 980.3 | 8.34 | 10.39 | 15.0 | 0.216 | 8.52 | 25.7 | 42.4 | 7.81 | 23.46 | 38.88 | 24.42 |
| 211 | | 947 | 980.3 | 9.68 | 10.41 | 25.0 | 0.367 | 8.48 | 19.0 | 44.1 | 7.66 | 17.16 | 39.83 | 41.28 |
| 212 | | 947 | 980.3 | 9.93 | 11.12 | 50.0 | 0.734 | 12.71 | 21.3 | ---- | 11.45 | 19.19 | ---- | 85.49 |
| 213 | WAINWRIGHT CRUDE | 987 | 1021.7 | 9.28 | 9.16 | 7.5 | 0.110 | 8.50 | 24.8 | ---- | 7.71 | 22.49 | ---- | 13.64 |
| 214 | | 947 | 980.3 | 9.34 | 6.06 | 800.0 | 11.502 | 41.47 | 52.1 | 65.2 | 37.60 | 47.23 | 59.11 | 1509.0 |
| 215 | | 820.7 | 873.1 | 9.41 | 6.40 | 100.0 | 1.438 | 23.80 | 36.55 | 50.3 | 21.56 | 33.11 | 45.56 | 199.0 |
| 216 | | 1027.5 | 1045.3 | 9.10 | 7.02 | 80.0 | 1.169 | 23.77 | 35.0 | 44.8 | 21.60 | 31.81 | 40.72 | 162.6 |
| 217 | → | 1132.9 | 1132.0 | 7.30 | 7.36 | 200.0 | 2.876 | 33.37 | 45.4 | 49.6 | 30.94 | 42.09 | 45.99 | 375.0 |
| 218 | | 1027.5 | 1045.3 | 7.03 | 9.22 | 400.0 | 5.870 | 31.04 | 49.1 | 52.5 | 28.86 | 45.65 | 48.81 | 761.4 |
| 219 | | 947 | 980.3 | 7.13 | 8.03 | 600.0 | 8.627 | 16.22 | 34.7 | 39.5 | 15.06 | 32.23 | 36.68 | 1022.5 |
| 220 | | 1083.0 | 1085.2 | 7.18 | 9.36 | 800.0 | 11.502 | 31.10 | 41.5 | 45.7 | 28.87 | 38.52 | 42.42 | 1300.76 |
| 221 | | 1027.5 | 1045.3 | 5.40 | 13.24 | 800.0 | 11.739 | 33.33 | 39.8 | 42.2 | 31.09 | 37.13 | 39.37 | 1215.44 |

2. Possible wettability changes are eliminated from run to run because the oil is not in contact with the rock for long periods of time as is the case if numerous runs are conducted on the same sandpack.


Material balance problems are present although they were not severe over the course of a run. By scanning some of the tabulated data in Appendix D, it can be seen in some runs that the average saturation (material balance calculation) sometimes decreases for one step and then continues to increase. As we inject water and produce oil and water this saturation calculation should always be increasing until the ultimate oil recovery is reached, so a decrease in this average saturation column indicates a slight material balance error. In the case of Wiborg²³ this cause of error should not be great since most of his runs were terminated just past breakthrough. However, in this set of experiments production was continued far past breakthrough and in some runs, possibly one hundred centrifuge tubes would have to be read and the errors could build over this length of time. This should not cause serious problems if the material balance is only kept for one run.

The problem of wettability changes in unaged cores is a major one if more than one run is to be made on the same sandpack. The Dow Corning fluid is especially bothersome in this respect. It was found that a short period of

aging (about 15 days) reversed the wettability of the sand-pack from water-wet to oil-wet. Run 401 was saturated and then left for about 15 days before the displacement experiment was run. When this point was plotted on Figure 2 it was very anomalous with respect to the rest of the data. If the recovery curve of run 401 is compared with the curve of 402 (Figures B-22 and B-23, respectively) it can be seen that run 401 behaves quite differently from the other runs. The breakthrough recovery is very low and the subordinate recovery subsequent to breakthrough almost equals the breakthrough recovery. This is not characteristic of water-wet systems. Water-wet systems are characterized by a late breakthrough recovery with a very flat subordinate production history. All of the other curves with Dow Corning at low rates show the latter type of behavior and these were interpreted to be water-wet.

Further to this argument on wettability changes a study was carried out on the used sand from one of the tests. The used sand from the Dow Corning fluid runs was soaked in recommended solvents and then steamed and rinsed in soap and water in an attempt to see if it could be cleaned. A simple bench imbibition test showed that the used sand would not imbibe any water, whereas before it was used it would imbibe water spontaneously.

FIGURE 2
DOW CORNING FLUID
BREAKTHROUGH RECOVERY VS.
SCALING COEFFICIENT (I)




SCALING COEFF. (I)

The experimental results involving Dow Corning fluid are presented in Figure 2. The plot represents breakthrough recovery versus the scaling coefficient "I". The rate of injection was changed to vary the scaling coefficient. As the rate was increased a decrease was observed in the breakthrough recovery of some 10% of the oil in place. The experimental data were correlated by the use of the dimensionless "I" function which is a simplification of Geertsma's (L_t) function as explained earlier. Run 401 is anomalous when compared to the other data and was discussed previously.


The value of "I" was increased by increasing the rate of injection and holding the other parameters relatively constant. Although the data in the two inch core tends to be scattered at lower rates a general trend of decreasing recovery can be seen. This decrease in recovery has been attributed to viscous fingering within the core. From Equation (3), for the average peak to peak distance between fingers, an increasing displacement velocity and an increasing viscosity difference both decrease the distance between fingers, λ_m . Because of the large injection rates and large viscosity difference employed in this study the peak to peak distance of fingers should be very small.

It is interesting to note that the recovery from run 401 (at breakthrough), which was considered to be oil-wet, is very close to the recovery for the two four inch core

runs at high rates. This can be explained if the work of Raza et al.¹⁹ is examined. If the different displacement characteristics are studied in Figures 3 and 4 (reproduced from reference 19), a fundamental difference between waterflooding in an oil-wet and a water-wet system can be seen. In Figure 3, where the rock is water-wet, the invading water prefers to advance along the walls of the pores and likes the smaller pores as well, since the capillary forces are higher. When the end of a pore is reached the water cusps in at the outlet and traps a droplet of oil in the pore. In an oil-wet system (Figure 4) the water prefers to stay away from the solid surface and moves up the center of the larger pores thereby breaking through much earlier than in the water-wet case. It seems plausible that if water were injected into a water-wet core at a very high rate the water would not have time to imbibe around the edges of pores or into the smaller pores. The capillary forces at high rates would not be as important, thus imbibition into these smaller pores would probably not be accomplished before breakthrough. The path of least resistance would be followed in this case, right up the center of the pores. In this case, although the system is water-wet it behaves as though it were oil-wet for the first part of the flood. The water advances up the center of the pores at first like a flood in an oil-wet



DISPLACEMENT OF OIL BY WATER (water-wet sand, $\theta = 0^\circ$) FIG. 3.



DISPLACEMENT OF OIL BY WATER (oil-wet sand, $\theta = 180^\circ$) FIG. 4.



-taken from Raza et. al. (19.)

system. As the flood progresses, the system has more time to imbibe water into any smaller pores that were bypassed prior to breakthrough. So in the later stages of the flood, imbibition around the smaller corners of the pores is taking place as in a flood in a water-wet system. It should be mentioned that the wettability has not reversed, the system is only acting oil-wet at first. Craig⁶ states that at high rates of displacement wettability characteristics do not have time to manifest themselves which is in agreement with the preceding explanation.

Capillary end effects can be ruled out as an explanation for the decrease in breakthrough recovery observed. Because of the long system used and the large viscosity ratios used in this study capillary forces should be very small compared to the viscous forces. Rapoport and Leas¹⁸ show that the end effect diminishes as the rate of injection is increased. They also show that capillary forces decrease as the rate is increased until some stabilized value is reached. After some rate was exceeded they found the recovery was constant because of this stabilization of capillary forces in the flood front. At higher viscosity ratios they did observe a decrease in recovery but explained it as an inlet end effect. Because of the design of the end caps of the coreholders for this study and the size and length of the system these end effects are very small and would not

account for the 10% decrease in breakthrough recovery.


In Figure 5 the recoveries at water to oil ratios of 6 and 20 have been plotted versus the scaling group "I". The characteristic decline of the breakthrough recovery curve observed in Figure 2 was not observed. Only a very slight decrease, if any, can be seen at $WOR = 6$. The recovery at $WOR = 20$ is constant with no decrease observed.

This indicates that rate of injection is only affecting the recovery early in the life of the flood and as the flood progresses the effect of rate on recovery disappears.

In waterflooding a water-wet system the residual oil is trapped as globules in a discontinuous state (Figure 3), resulting in a small amount of subordinate production. Therefore, a low breakthrough recovery should result in a low ultimate recovery. From Figure 5 it is apparent that this is not the case. However, if the water flowed up the center of the pores at high rates of injection, at water breakthrough the remaining oil is left in a continuous state around the sand grains (Figure 4). As subsequent injection takes place the water has more time to imbibe around the sand grains. Substantial subordinate production could occur resulting in the same ultimate recovery as observed at low rates.

FIGURE 5
DOW CORNING 200
RECOVERY VS. SCALING COEFFICIENT (I)₀

* WOR=6
□ WOR=20



SCALING COEFF. (I)

D. DARCY LAW CROSS-PLOTS

Following a suggestion of Bentsen² a simple cross-plot using Darcy's Law was constructed for the two and four inch cores with Dow Corning fluid. If the injection rate, Q , is plotted versus the pressure drop, Δp , for the same average saturation in the core a straight line with slope, $KA/\mu L$, should result. The permeability, K , is considered to be a function of saturation only, so if the Q and Δp values are taken at the same value of W_i (dimensionless pore volumes injected) the average saturation should be comparable from run to run. If there is nothing affecting the behavior other than saturation, then these plots should be straight lines.

Figures 6 and 7 are the Darcy Law cross-plots. In these figures the rate of injection is plotted versus the pressure drop and points of equal volumes of water injected are joined. Each line then represents the same water saturation in the core at the different injection rates.

From Figures 6 and 7 there appears to be two distinct regions on the plots. Darcy's Law holds until some "critical" rate is exceeded at approximately 265 cc/hr and then the conductivity of the system continually decreases as rate is increased.

Figure 6 is a plot of the data obtained from the two inch cores and Figure 7 is a plot from the four inch core





FIGURE 6
DARCY LAW CROSSPLOT (2" CORE)
Q VS. ΔP
SLOPE = $Q = KA/\mu L = \text{CONDUCTANCE}$



data. The slopes differ by nearly a factor of four between Figures 6 and 7 which is to be expected since the ratio of cross-sectional areas is nearly four.

It was thought that these correlations might be used to explain the decrease in recovery in Figure 2. However, the break in the relationship does not correlate with the observed decrease in recoveries. The critical rate shown in Figures 6 and 7 is approximately 265 cc/hr. This rate corresponds to a scaling coefficient value of 0.3113 and is indicated by the arrow in Figure 2. Most of the decrease in recovery has already occurred before this change of conductivity takes place. It appears that this "critical" rate occurs very close to the rate where the breakthrough recovery levels off and becomes constant. At this point, according to Chouke⁴, there are numerous fingers in the system and recovery is independent of the scaling factor. Perhaps there is severe interference between the fingers after this point is surpassed so that the conductivity is continually decreasing and there is no effect of this decrease of conductivity on recovery. A changing mobility ratio could have some affect on these correlations, however, there was no evidence that such a change was taking place.

E. RELATIVE PERMEABILITY CALCULATIONS

In another attempt to see what changes occur from the low rates to the high rates of injection, the theory published by Johnson et al.¹¹ to calculate relative permeabilities from the unsteady state displacement data, known as the external drive technique, was employed. A complete derivation can be found in Appendix C as well as the "curves" generated by these calculations.

The values of relative permeabilities calculated by this technique are not considered reliable. Wild fluctuations appear that make fitting a curve through the points rather difficult. It was hoped that changes in the relative permeability curves would provide some additional evidence to explain the decreasing recovery observed. However, no conclusions could be drawn from these results.

Archer and Wong¹ suggest that the poor definition of permeability can be encountered in strongly water-wet homogeneous cores. These anomalous curve shapes may be associated with laboratory-observed water breakthrough occurring at a different time than actual water arrival at the down stream end of the core.

F. CALCULATION OF THE CHOUKE CONSTNAT

From Figure 2 the point of decrease in recovery on the curve corresponds to a scaling value of 0.015 and if


this value is used in Equation (6) the value of the Chouke constant (C) can be calculated. If C can be found for a system then a prediction as to where fingering begins can be made.

There are two distinct sets of permeabilities present in the Dow Corning runs, one averaging 15.92 darcies and the other set averaging 8.3 darcies. For the 15.92 darcies set C was calculated to be 118 and for the 8.3 darcies set C was calculated to be 139. These are much higher values than those calculated by either Wiborg²³ or Kloepper¹³ and much lower than the value reported by Collins⁵ (see Table 3).

de Haan⁷ suggests that at low values of initial water saturation they obtained values of C around 100 which seems to fit well with the values found in this study. However, C is a constant only for one particular system. From Table 3, it is apparent that no generalizations can be made for assuming a value for C and calculating the point when fingering will begin in a system.


G. CALCULATION USING THE van MEURS AND van der POEL THEORY

The theory of van Meurs and van der Poel²¹ was covered in detail by Wiborg²³. The theory developed is based on an idealized picture of water fingers as shown in Figure 8. The areas occupied by the fingers and the areas occupied by the immobile oil and water can be stated in



IDEALIZED PICTURE OF WATER FINGERS
SHOWING PROTRUSIONS AND OIL POCKETS

OIL



WATER

TABLE 3

CALCULATION OF C

| <u>Researcher</u> | <u>Viscosity Ratio</u> | <u>C</u> | <u>Sw_i</u> |
|-------------------|----------------------------|----------|-----------------------|
| Wiborg (CWO) | 15.5 | 27.7 | .15 -.30 |
| (MCT 5) | 34.2 | 24.3 | .12 -.25 |
| (DOW CORNING) | 111.4 | 39.4 | .09 |
| Kloepfer | 6.4 | 64 | .10 |
| Collins | 292 | 250 | .13 |
| de Haan | 4 & 25 | 30 | - |
| this study | 533 | 118-139 | .11 |

TABLE 4

van MEURS RECOVERY CALCULATION (FRACTION P.V.)

$$So_r = 0.45$$

$$M = 533$$

| <u>W_i</u> | <u>Experimental Np</u> | <u>Sw_m = Sw_i</u> | | <u>Sw_m = 0.15</u> | |
|----------------------|----------------------------|--|-------------|------------------------------|-------------|
| | | <u>Calc. Np</u> | <u>Δ Np</u> | <u>Calc. Np</u> | <u>Δ Np</u> |
| B.T. | .1442 | .1343 | -.0099 | .1721 | +.0279 |
| 0.320 | .1579 | .1454 | -.0125 | .1796 | +.0217 |
| 0.928 | .2583 | .1670 | -.0913 | .2003 | -.0580 |
| 1.436 | .2964 | .1795 | -.1169 | .2123 | -.0841 |
| 2.445 | .3461 | .1985 | -.1476 | .2305 | -.1156 |
| 3.487 | .3790 | .2140 | -.1650 | .2452 | -.1338 |

terms of the saturations of these respective areas.

- Area 1: represents the area outside the water fingers where oil flows unhindered.
- Area 2: represents the center area of the fingers where the water flows unhindered.
- Area 3: represents the area consisting of the edge zones of all the water fingers of the cross-section. In this area both water and oil are immobile.

Area 1 can be represented by the difference between the oil saturation and the residual oil saturation ($S_o - S_{o_r}$) or with $S_o + S_w = 1$ then Area 1 is equal to $1 - S_o - S_w$. Area 2 could be represented by the difference between the water saturation and the immobile water saturation in Area 3 ($S_w - S_{w_m}$). Using these relations and following the theory an expression for the breakthrough recovery is obtained where the recovery is expressed as a fraction of the pore volume.

The breakthrough recovery is given by:

$$Np_b = \frac{A^2}{MB}$$

and recovery after breakthrough is given by:

$$Np = S_{w_m} + \frac{1}{M-1} [2\sqrt{W_i MB} - W_i - B]$$

where

$$\begin{aligned}
 Np_b &= \text{breakthrough recovery (\% P.V.)} \\
 Np &= \text{recovery after breakthrough (\% P.V.)} \\
 A &= \sqrt{(M-1)B} Sw_m + B \\
 B &= 1 - So_r - Sw_m \\
 M &= \mu_o / \mu_w \\
 W_i &= \text{pore volumes injected}
 \end{aligned}$$

The theory is developed with the assumption that fingers have already formed in the system and therefore this calculation should not be expected to predict the entire curve in Figure 2. It should only be expected that this theory would predict recoveries at the lower end of the curve where fingers are fully developed. To apply the theory a value for Sw_m must be found. A good first approximation would be to use the initial water saturation, and previous researchers have done this. However, if the fingers in Figure 8 are studied and if the fingers are considered to be without protrusions it can be seen that the value of immobile water in Area 3 is already Sw_i . With protrusions from the water fingers, the value of Sw_m must be somewhat higher than Sw_i .

van Meurs et al.²¹ found that the theory correlated best with their experimental data when $Sw_m = 0.15$. For this study, first the calculation was performed using the value


of Sw_i for Sw_m and then another calculation was performed using $Sw_m = 0.15$. A value for So_r was obtained from run 202 where 7.2 pore volumes had been injected. Using this value of So_r and the two selected values of Sw_i the calculated performance for these two cases was compared with the experimental performance of run 205. Run 205 was one of the experiments conducted at higher displacement rates. The results of the calculation are listed in Table 4.

The breakthrough recovery is within 1% of the experimental value when using $Sw_i = Sw_m$ but the subsequent production history does not compare with the observed results. As the flood progressed the separation between experimental values and theoretical values increased. The theoretical values are compared with the experimental values in Figure 9. The subsequent recovery calculation produces a very flat profile as compared to the actual experimental data. From the calculations only about 8% of the pore volume is produced after breakthrough up to a $W_i = 3.487$ whereas the experimental results show 23.5% produced after breakthrough.

For $Sw_m = 0.15$ the breakthrough recovery could not be predicted nor could the subsequent production history. The same flat recovery profile is predicted but the breakthrough recovery is too high and the subsequent production predicted is too low.

Although the theory predicted the breakthrough recovery in the one case, the predicted recoveries after breakthrough

FIGURE 9.
RECOVERY HISTORY
RUN- 205
FLUID- DOW CORNING 200
FLOW RATE: 800.0 CC/HR



showed substantial error. Wiborg²³ could only predict the breakthrough recovery for one of his three oils using this method. From Figure 9 it should be noted that the small increase in the breakthrough recovery was present for both assumptions of Sw_m . This very flat profile is characteristic of systems with low mobility ratios. Possibly their theory may be more applicable to systems which exhibit lower mobility ratios.


H. DISPLACEMENT TESTS WITH WAINWRIGHT CRUDE OIL

A second set of displacement experiments were run using a Wainwright crude oil in an attempt to observe the phenomenon of decreasing recovery for a more viscous crude oil. The oil had been dewatered to remove about 6% water that was contained within the crude when obtained from the stock tank.

The rates of displacement varied from 7.5 cc/hr to 800 cc/hr, which was practically the same range that was studied using the Dow Corning fluid. A summary of the displacement test data appears as the lower one-half of Table 2 and the complete recovery histories are tabulated in Appendix D. The individual recovery history curves can be found in Appendix B.

From Table 2 the oil viscosity can be seen to fluctuate much more than the viscosity of the Dow Corning fluid,

FIGURE 10.
MAINWRIGHT CRUDE OIL
BREAKTHROUGH RECOVERY VS.
SCALING COEFFICIENT (I)



but as was pointed out earlier in the discussion, the range of variation in this parameter does not seem to affect the results.

In Figure 10 the breakthrough recoveries are plotted versus the scaling coefficient "I" for the Wainwright crude oil. Again the scaling coefficient was varied by increasing the rate of injection with other parameters being held constant. As the rate of injection was increased the breakthrough recoveries increased dramatically over the range of rates studied. The observed behavior was contrary to what was expected after having just observed the behavior of the Dow Corning fluid. However, this increase in recovery has been attributed to water-in-oil emulsions being formed in-situ. Microscope photographs of the emulsions produced during run 220 can be seen in Figures 11 and 12.

Crude oil was produced until breakthrough of the emulsion. Pure water did not breakthrough before the emulsion in any of the runs. Once breakthrough of the emulsion had occurred all further oil production was in the form of this emulsion. Later in the life of the flood, pure water drops were produced between slugs of emulsion. The produced emulsion was found to contain 53.2% water by volume in a sample from one of the runs. The emulsion properties were not continuously monitored.




FIG. 11. Water-in-Oil Emulsion
Produced Run 220. Mag. (400x)




FIG. 12. Water-in-Oil Emulsion
Produced Run 220. Mag. (650x)

Wiborg²³ has also noted some emulsion formation in his experiments and stated two mechanisms which account for the increased recovery by emulsion formation:

1. the viscosity ratio between the displacing front and the displaced oil decreases since the viscosity of the emulsion approaches that of the external phase,
2. partial blocking of the paths of low resistance thereby leading to an improved pore volume sweep efficiency.

Generally it was found that the stability of the emulsion increased as the rate increased and as the permeability decreased. The emulsion produced from run 214 appeared to be the hardest to break. Extra varsol and extra centrifuging was needed to separate the phases. The emulsion produced during runs 219 and 212 was not difficult to break.

At low values of the scaling coefficient represented by runs 210, 211 and 213, the breakthrough recovery was constant. No emulsions were produced on these three runs. Emulsions were produced in all other runs and increased breakthrough recoveries were found on all these runs. Runs 214, 215, 216 and 217 have the lowest Ko_i values (see Table 2) averaging around 8 Darcy. These runs appear to place an upper bound on the breakthrough recoveries as shown by the curve in Figure 10. This curve will be

referred to as the 8 Darcy curve. Data points that fall below this line are for cores which had larger permeabilities.

If Table 2 is examined, a change in initial water saturations is noted. Runs 210 through 216 have initial water saturations averaging slightly greater than 9%. In runs 217 through 220 the initial water saturation was constant at a level near 7%.

Run 221 shows a very low water saturation of 5.4% and earlier in the discussion it was noted that this core had a high porosity value compared with the other cores. It was felt that an error had been made in the porosity determination which would also affect the saturations. The results of this run cannot be interpreted with confidence.

It should be noted that the recoveries for all runs that fall off the curve in Figure 10 have 7% initial water saturation present. Also those runs that fall off the curve have larger permeabilities than those that form the upper bound of the 8 Darcy curve in Figure 10.

Either one of the following two conditions might explain the scattering of results:

1. As the permeability increases the tortuosity of the flow paths decreases and the mixing action and shear stresses in the core are not as great and therefore a


less stable emulsion is formed.

2. The higher water saturation could promote better mixing since it has been shown that the connate water forms a bank in front of the injection water²⁴. It is connate water which actually displaces the oil; therefore, if more connate water is available possibly a more stable emulsion might be formed.

More tests under more controlled conditions are needed before a decision can be made on which mechanism is responsible for the emulsion stability.

The data for the Wainwright crude oil were correlated in a Darcy Law cross-plot similar to that for the Dow Corning fluid. These results are presented in Figure 13. Here the rate of injection is plotted versus the pressure drop across the system. If Darcy's Law is valid this should yield a straight line with the slope equal to the conductance of the system. Each line represents a constant amount of water injected and therefore a constant saturation in the cores at the different rates studied.

From Figure 13 there appears to be a straight line at low displacement rates. At a rate of approximately 50 cc/hr the plots deviate from the straight line. This rate corresponds to the rate where emulsions were first noted in the system and the subsequent increase in recovery in Figure 10.



The breaks in the relationships shown in Figure 13 show that the conductance of the system seems to be erratic after the emulsions are formed. This might support the fact that emulsions are being formed in-situ and are affecting the conductance in this manner. This variation in conductance could also indicate that the emulsions are not uniform from core to core.

VI. OBSERVATIONS AND CONCLUSIONS

Based on the results of this study the following observations and conclusions may be drawn:

1. An increase in flooding velocity for tests on cores containing a synthetic Dow Corning fluid caused a decrease in breakthrough recovery of about 10%.
2. A region of apparent non-Darcy flow was found in the Dow Corning system at injection rates greater than approximately 265 cc/hr. However, this did not explain the decrease in recovery noted with the Dow Corning fluid since most of the decrease was observed at lower rates.
3. Emulsion formation appears to be an extremely effective recovery mechanism. A five-fold increase in breakthrough recovery was noted for the Wainwright crude oil over the range of rates investigated.
4. The stability of the emulsions formed appeared to be sensitive to either the permeability of the system or the amount of initial water saturation or both.
5. The Dow Corning fluid initiated a wettability reversal in one core when the saturated core was aged for a period of 15 days.

6. Relative permeabilities calculated by the external drive technique appear to be unreliable. Wide fluctuations in the calculated data appear even when smoothing of the input data was performed.

VII. RECOMMENDATIONS

- * The sand used for displacement tests should either be sorted to narrower grain size range or a number of shipments thoroughly mixed so that the grain size for the entire series is more uniform. The sandpack properties should then be reproducible.
- * The permeability should be carefully controlled and a complete series of runs obtained for a number of different permeabilities to ascertain the nature of the sensitivity of emulsion formation to permeability.
- * The idea of injecting a slug of emulsion and then waterflooding should be examined to improve sweep efficiencies at lower more reasonable rates.
- * Tests should be initiated on sandpacks that have more realistic field permeabilities to see what rates must be exceeded to produce emulsions under these conditions.
- * A number of closely controlled tests with a number of permeabilities and a complete range of rates may lead to a correlation for predicting this "critical" rate where non-Darcy flow starts.
- * More detail must be obtained in the region where the flow changes to non-Darcy to determine if this is a transition region or a sharp break.

- * The idea that wetting conditions cannot manifest themselves at high rates deserves to be examined more closely. Perhaps a complete series on similar systems except that one be oil-wet and one be water-wet would provide some clues.

NOMENCLATURE

$$A = \sqrt{(M-1)B S_{w_m}} + B$$

$$B = 1 - S_{o_r} - S_{w_m}$$

$$C = \text{CHOUKE constant (dimensionless)}$$

$$D = \text{diameter of tube (cm)}$$

$$f_o = \text{fraction of oil flowing from system}$$

$$f_w = \text{fraction of water flowing from system}$$

$$g = \text{gravitational constant}$$

$$I = \frac{LV\mu_w}{\sigma\sqrt{K}}, \text{ dimensionless group}$$

$$I_R = \text{relative injectivity}$$

$$I.O.I.P. = \text{initial oil in place}$$

$$K = \text{absolute permeability (darcy)}$$

$$K_o = \text{effective permeability to oil (darcy)}$$

$$K_w = \text{effective permeability to water (darcy)}$$

$$K_{ro} = \text{relative permeability to oil}$$

$$K_{rw} = \text{relative permeability to water}$$

| | | |
|-----------|---|--|
| L | = | length of tube |
| L_t | = | $\frac{\sigma \cos \theta \sqrt{K/\phi}}{LV\mu_w}$, dimensionless group |
| M | = | viscosity ratio |
| N_p | = | cumulative oil production (cc) |
| N_{p_b} | = | recovery at water breakthrough (cc) |
| P_c | = | capillary pressure (atm) |
| P_o | = | pressure in oil phase (atm) |
| P_w | = | pressure in water phase (atm) |
| Q | = | injection rate (cc/hr) |
| q_o | = | oil flow rate (cc/sec) |
| q_w | = | water flow rate (cc/sec) |
| S_1 | = | inlet saturation in terms of wetting phase |
| S_2 | = | outlet saturation in terms of wetting phase |
| S_o | = | oil saturation |
| S_{o_r} | = | residual oil saturation |
| S_w | = | water saturation |
| S_{w_f} | = | water saturation at flood front |

| | | |
|----------------|---|--|
| S_{w_i} | = | initial water saturation |
| S_{w_m} | = | immobile water saturation |
| $V=u$ | = | total flow rate per unit cross sectional area, cm/sec |
| W_i | = | pore volumes injected, dimensionless |
| λ_{cr} | = | critical wavelength (cm) |
| λ_m | = | average wavelength (cm) |
| μ_o | = | viscosity of oil (poise) |
| μ_w | = | viscosity of water (poise) |
| σ | = | interfacial tension (dynes/cm) |
| θ | = | wetting angle |
| ϕ | = | porosity |
| ρ_o | = | density of oil (gm/cc) |
| ρ_w | = | density of water (gm/cc) |

REFERENCES

1. Archer, J.S. and Wong, S.W., "Use of a Reservoir Simulator To Interpret Laboratory Waterflood Data." SPE Journal, 13, No. 6, 343-347.
2. Bentsen, R.G., Private Communication, Sept. 1977, University of Alberta.
3. Breton, J.N. and Hughes, R.V., "Relation Between Pressure and Recovery in Long Core Water Floods," Trans. AIME (1949), 186, 100.
4. Chouke, R.L., van Meurs, P. and van der Poel, C., "The Instability of Slow, Immiscible, Viscous Liquid-Liquid Displacements in Permeable Media," Trans. AIME (1959), 216, 188.
5. Collins, H.N., "High Viscosity Crude Oil Displacements In A Long Unconsolidated Sand Pack Using A Native Brine," M.Sc. Thesis, University of Alberta (1964).
6. Craig, F.F., Jr., "The Reservoir Engineering Aspects of Waterflooding," SPE Monograph, Vol. 3, Henry L. Doherty Series, (1971).
7. de Haan, H.J., "Effect of Capillary Forces in the Water-Drive Process," Proc. 5th World Petroleum Congress, Sec. 2, 25, (1959).
8. Dykstra, H. and Parsons, R.L., "The Prediction of Oil Recovery by Waterflood," Secondary Recovery of Oil in the United States, API, (1950).
9. Earlougher, R.C., "Relationship Between Velocity, Oil Saturation and Flooding Efficiency," Trans. AIME (1943), 153, 125.
10. Engelberts, W.F. and Klinkenberg, L.J., "Laboratory Experiments of the Displacement of Oil by Water From Packs of Granular Material", Proc. 3rd. World Petroleum Congress, Sec. 2, 544, (1952).

11. Johnson, E.F. and Bossler, D.P. and Naumann, V.O., "Calculation of Relative Permeability from Displacement Experiments", Trans. AIME (1959), 216, 370.
12. Geertsma, J., Croes, G.A. and Shwarz, N., "Theory of Dimensionally Scaled Models of Petroleum Reservoirs," Trans. AIME (1956), 207, 118.
13. Kloepper, J.G., "Viscous Fingering in Unconsolidated Cores," M.Sc. Thesis, University of Alberta, (1975).
14. Kyte, J.R. and Rapoport, L.A., "Linear Waterflood Behavior and End Effects in Water-Wet Porous Media," Trans. AIME (1958), 213, 423.
15. Miller, F.G., "A Laboratory Study of Water Encroachment in Oil Filled Sand Columns," U.S. Bureau of Mines, R.I. 3595, 19, (1941).
16. Morse, R.A. and Yuster, S.T., "Waterflood Tests on Long Cores," Prod. Monthly, (Dec. 1946).
17. Perry, R.H. and Chilton, C.H., "Chemical Engineers Handbook," fifth edition, McGraw-Hill Book Company.
18. Rapoport, L.A. and Leas, W.J., "Properties of Linear Waterfloods," Trans. AIME (1953), 198, 139.
19. Raza, S.H., Treiber, L.E. and Archer, D.L., "Wettability of Reservoir Rocks and Its Evaluation," Prod. Monthly, (April 1968), 2.
20. Ryder, H.M., "Effects of High Flooding Pressure," Prod. Monthly, (Dec. 1937).
21. van Meurs, P. and van der Poel, C., "A Theoretical Description of Water Drive Processes Involving Viscous Fingering," Trans. AIME (1958), 213, 103.
22. Welge, H.J., "A Simplified Method for Computing Oil Recovery by Gas or Water Drive," Trans. AIME, 195, 91, (1952).

23. Wiborg, R., "Frontal Instabilities When Waterflooding at Unfavourable Viscosity Ratios," M.Sc. Thesis, University of Alberta, (1976).
24. Flock, D.L., Personal communication, results from the University of Alberta Petroleum Engineering Laboratory.

APPENDIX A

FLUID PROPERTIES

FLUIDS:

DOW CORNING 200 @ 74°F

Interfacial tension - 34.04 dynes/cm

density - 0.9691 gm/cc

WAINWRIGHT CRUDE OIL @ 74°F

Interfacial tension - 26.97 dynes/cm

density - 0.9974 gm/cc

FIGURE A-1
VISCOSITY-TEMPERATURE PROFILE
WATER
-FROM PERRY AND CHILTON
(CHEMICAL ENGINEERS HANDBOOK)




FIGURE A-2
VISCOSITY-TEMPERATURE PROFILE
DOW CORNING 200 (500CS)




FIGURE A-3
VISCOSITY-TEMPERATURE PROFILE
WAINWRIGHT CRUDE OIL
(WATER REMOVED)





FIGURE A-4
DENSITY VS. TEMPERATURE
* WAINWRIGHT CRUDE OIL
◇ DOW CORNING 200 FLUID
+ WATER



APPENDIX B

RECOVERY HISTORY CURVES

FIGURE B-1
RECOVERY HISTORY
RUN- 201
FLUID- DOW CORNING 200
FLOW RATE: 2.5 CC/HR




FIGURE B-2
RECOVERY HISTORY
RUN- 202
FLUID- DOW CORNING 200
FLOW RATE: 10.0 CC/HR



FIGURE B-3
RECOVERY HISTORY
RUN- 203
FLUID- DOW CORNING 200
FLOW RATE: 160.0 CC/HR



FIGURE B-4
RECOVERY HISTORY
RUN- 204
FLUID- DOW CORNING 200
FLOW RATE: 300.0 CC/HR




FIGURE B-5
RECOVERY HISTORY
RUN- 205
FLUID- DOW CORNING 200
FLOW RATE: 800.0 CC/HR




FIGURE B-6
RECOVERY HISTORY
RUN- 206
FLUID- DOW CORNING 200
FLOW RATE: 20.0 CC/HR




FIGURE B-7
RECOVERY HISTORY
RUN- 207
FLUID- DOW CORNING 200
FLOW RATE: 560.0 CC/HR




FIGURE B-8
RECOVERY HISTORY
RUN- 208
FLUID- DOW CORNING 200
FLOW RATE: 50.0 CC/HR




FIGURE B-9
RECOVERY HISTORY
RUN- 209
FLUID- DOW CORNING 200
FLOW RATE: 15.0 CC/HR




FIGURE B-10

RECOVERY HISTORY

RUN- 210

FLUID-WAINWRIGHT CRUDE

FLOW RATE: 15.0 CC/HR




FIGURE B-11
 RECOVERY HISTORY
 RUN- 211
 FLUID-WAINWRIGHT CRUDE
 FLOW RATE: 25.0 CC/HR




FIGURE B-12
RECOVERY HISTORY
RUN- 212
FLUID-WAINWRIGHT CRUDE
FLOW RATE: 50.0 CC/HR



FIGURE B-13
RECOVERY HISTORY
RUN- 213
FLUID-WAINWRIGHT CRUDE
FLOW RATE: 7.5 CC/HR



FIGURE B-14
RECOVERY HISTORY
RUN- 214
FLUID-WAINWRIGHT CRUDE
FLOW RATE: 800.0 CC/HR




FIGURE B-15
 RECOVERY HISTORY
 RUN- 215
 FLUID-WAINWRIGHT CRUDE
 FLOW RATE: 100.0 CC/HR




FIGURE B-16
RECOVERY HISTORY
RUN- 216
FLUID-WAINWRIGHT CRUDE
FLOW RATE: 80.0 CC/HR




FIGURE B-17
RECOVERY HISTORY
RUN- 217
FLUID-WAINWRIGHT CRUDE
FLOW RATE: 200.0 CC/HR




FIGURE B-18
 RECOVERY HISTORY
 RUN- 218
 FLUID-WAINWRIGHT CRUDE
 FLOW RATE: 400.0 CC/HR



FIGURE B-19
RECOVERY HISTORY
RUN- 219
FLUID-WAINWRIGHT CRUDE
FLOW RATE: 600.0 CC/HR




FIGURE B-20
RECOVERY HISTORY
RUN- 220
FLUID-WAINWRIGHT CRUDE
FLOW RATE: 800.0 CC/HR




FIGURE B-21
 RECOVERY HISTORY
 RUN- 221
 FLUID-WAINWRIGHT CRUDE
 FLOW RATE: 800.0 CC/HR



FIGURE B-22
RECOVERY HISTORY
RUN- 401
FLUID- DOW CORNING 200
FLOW RATE: 10.0 CC/HR



FIGURE B-23
RECOVERY HISTORY
RUN- 402
FLUID- DOW CORNING 200
FLOW RATE: 40.0 CC/HR



FIGURE B-24
RECOVERY HISTORY
RUN- 403
FLUID-DOW CORNING 200
FLOW RATE: 600.0 CC/HR





FIGURE B-25
RECOVERY HISTORY
RUN- 404
FLUID- DOW CORNING 200
FLOW RATE: 1120.0CC/HR



APPENDIX C

RELATIVE PERMEABILITY CALCULATIONS

RELATIVE PERMEABILITY CALCULATIONS

The method employed is an extension of the Welge²² method for finding the relative permeability ratios. It was presented by Johnson et al.¹¹

Two conditions must be met before the method is applicable:

(i) stabilized displacement

(ii) flow velocity is constant at all cross-sections.

The first condition implies that the pressure drop across the core be large enough to negate any capillary end effects or ensure that the zone where capillary effects dominate is compressed to a small fraction of the pore space. Implicit in the second condition is immiscible and incompressible fluids and a homogeneous and linear system.

Following the procedure of Leverett^{*} for the oil phase

$$q_o = - \frac{K_o}{\mu_o} \left[\frac{\partial P_o}{\partial X} - g \rho_o \sin \alpha \right] \quad (1)$$

and for the water phase

$$q_w = - \frac{K_w}{\mu_w} \left[\frac{\partial P_w}{\partial X} - g \rho_w \sin \alpha \right] \quad (2)$$

at any point in the core

$$q_t = q_o + q_w$$

* Leverett, M.C., Trans. AIME (1939), 132, 149.

and Equations (1), (2) and (3) can be combined to obtain

$$f_w = \frac{q_w}{q_t} = \frac{1 + \frac{K_o}{q_t \mu_o} \left\{ \frac{\partial P_c}{\partial X} - g \Delta \rho \sin \alpha \right\}}{1 + \frac{K_o \mu_w}{K_w \mu_o}} \quad (3)$$

where
$$\frac{\partial P_c}{\partial X} = \frac{\partial P_o}{\partial X} - \frac{\partial P_w}{\partial X} \quad (4)$$

and
$$\Delta \rho = \rho_w - \rho_o$$

for a horizontal system; $\sin \alpha = \sin 0 = 0$

and using the assumption that the pressure drop across the system is large enough to negate the capillary pressure gradient, the shortened form of the fractional flow equation is obtained;

as
$$\frac{\partial P_c}{\partial X} \rightarrow 0$$

$$f_w = \left[1 + \frac{K_o \mu_w}{K_w \mu_o} \right]^{-1} \quad (5)$$

or
$$f_o = 1 - f_w = \left[1 + \frac{K_w \mu_o}{K_o \mu_w} \right]^{-1} \quad (6)$$

from Buckley and Leverett^{*}; the material balance on a thin slice of the reservoir is

$$v \frac{\partial f_w}{\partial X} = \frac{\partial S}{\partial t} = 0 \quad (7)$$

and since f_w is a function of S only we may write

$$\frac{\partial f_w}{\partial X} = \frac{df_w}{dS} \frac{\partial S}{\partial X} \quad (8)$$

* Buckley, S.E. and Leverett, M.C., Pet. Tech., May, 1941.

now by substituting Equation (8) into (7)

$$v \frac{df_w}{dS} = \frac{-\frac{\partial S}{\partial t}}{\frac{\partial S}{\partial X}} = \left(\frac{\partial X}{\partial t} \right)_S = \left(\frac{\Delta X}{\Delta t} \right)_S = v f'_w \quad (9)$$

where $f'_w = \frac{df_w}{dS}$

by evaluating Equation (9) at the outflow face

$$\frac{L}{\Delta t} = v f'_w \quad \text{or} \quad \frac{1}{f'_w} = \frac{\Delta t v}{L} = \frac{\Delta t q}{\phi AL} = W_i \quad (10)$$

the average water saturation in the core could be taken as

$$S_{av} = \frac{\int_1^2 S dx}{L} \quad (11)$$

and from Equation (10) it is apparent that the distance a fixed saturation moves in the core is proportional to f'_w and then L could be represented by f'_{w2}

$$\text{therefore } S_{av} = \frac{\int_1^2 S df_w}{f'_{w2}} \quad (12)$$

This equation can be integrated by parts to yield

$$S_{av} = \frac{f'_w S \Big|_1^2 - \int_1^2 f'_w ds}{f'_{w2}} = \frac{f'_{w2} S_2 - f'_{w1} S_1 - \int_1^2 f'_w ds}{f'_{w2}} \quad (13)$$

but $S_1 \approx 1$, therefore $f'_{w1} = 0$.

then
$$S_{av} = S_2 - \frac{\int_1^2 df_w}{f_{w2}'} = S_2 - \frac{f_{w2} - 1}{f_{w2}'} \quad (14)$$

or
$$S_{av} = S_2 + f_{o2} W_i \quad (15)$$

at any particular instant the pressure drop across the core could be given as

$$\Delta P = - \int_1^2 \frac{\delta P}{\delta X} dx \quad (16)$$

also from Darcy

$$q = \frac{-KA}{\mu} \frac{\delta P}{\delta X} \quad \text{or} \quad f_o u = \frac{-KK_{ro}}{\mu_o} \frac{\delta P}{\delta X} \quad (17)$$

substitution of Equation (17) into (16) yields

$$\Delta P = \int_1^2 \frac{f_o u \mu_o}{K K_{ro}} dx = \frac{u \mu_o}{K} \int_1^2 \frac{f_o}{K_{ro}} dx \quad (18)$$

again by making use of the fact that the distance travelled in the core by a particular displacing saturation is proportional to f_w , Equation (18) may be written as

$$\int_1^2 \frac{f_o}{K_{ro}} dx = \int_0^{f_{w2}'} \frac{f_o}{K_{ro}} df_w' = \frac{\Delta P K f_{w2}'}{u \mu_o L} = f_{w2}' \frac{u_s / \Delta P_s}{u / \Delta P} = \frac{f_{w2}'}{I_r} \quad (19)$$

An expanded explanation of Equation (18) is essential since the steps involved may not be evident.

The group $\frac{\Delta P K}{u \mu_o L}$ is known as the reciprocal of the

relative injectivity (I_R). The relative injectivity is dimensionless and describes how the intake capacity ($u/\Delta P$) changes with cumulative injection. I_R is simply a comparison of the intake capacity at any time to the intake capacity at the start of the flood. It can be developed as follows:

$$q_o = \frac{K_o A \Delta P}{\mu_o L} \quad \text{or} \quad u = \frac{K_o \Delta P}{\mu_o L}$$

at the start of a flood

$$\frac{u_s}{\Delta P_s} = \frac{K_o}{\mu_o L} \quad (20)$$

Also at the very start of a flood, for all practical purposes, only oil is flowing ($K_o = K$).

$$\text{therefore, } \frac{u_s}{\Delta P_s} = \frac{K}{\mu_o L}$$

At any point in the flood the intake capacity is equal to the velocity (u) at that time over the pressure drop (ΔP) at that time.

$$\left(\frac{u}{\Delta P} \right)_t = \frac{u}{\Delta P} \quad (21)$$

now

$$I_R = \frac{u/\Delta P}{u_s/\Delta P_s} = \frac{u/\Delta P}{K/\mu_o L} = \frac{u \mu_o L}{K \Delta P} \quad (22)$$

the reciprocal of this group is present in Equation (19).

So from Equation (19),

$$\frac{f_{w2}'}{I_R} = \int_0^{f_{w2}'} \frac{f_o}{K_{ro}} df_w'$$

If we differentiate with respect to f'_{w2} Equation (19) becomes.

$$\frac{d(f'_{w2}/I_R)}{d(f'_{w2})} = \frac{f_o}{K_{ro}} \quad (23)$$

From Equation (10) $W_i = 1/f'_{w2}$, therefore Equation (23) becomes

$$\frac{d(1/W_i I_R)}{d(1/W_i)} = \frac{f_o}{K_{ro}} \quad (24)$$

if f_o is known Equation (24) could be solved for K_{ro} . The fraction of oil flowing out of the system could be calculated by noting that the oil flowing out of the system must equal the change in the average saturation in the core over the change in the cumulative amount of water injected, so the fraction of oil in the producing stream at any time may be calculated from

$$f_{o2} = \frac{dS}{d W_i} \quad (25)$$

and the K_{ro} can be found from Equation (24). Also by combining Equations (5) and (6)

$$\frac{f_w}{f_o} = \frac{K_w \mu_o}{K_o \mu_w} = \frac{K_{rw} \mu_o}{K_{ro} \mu_w} \quad (26)$$

which can be rearranged to yield K_{rw} .

$$K_{rw} = \frac{(1 - f_o)}{f_o} \frac{\mu_w}{\mu_o} K_{ro}$$

The procedure is to fit a curve to a S vs. W_i plot and

evaluate $\frac{dS}{d\bar{w}_i}$ and also fit a curve to $\frac{1}{\bar{w}_i I_R}$ vs. $\frac{1}{\bar{w}_i}$ plot

to evaluate $\frac{d\left(\frac{1}{\bar{w}_i I_R}\right)}{d\left(\frac{1}{\bar{w}_i}\right)}$ so that the calculation of K_{ro} and

K_{rw} is possible.

FIGURE C- 1




FIGURE C- 2




FIGURE C- 3




FIGURE C- 4




FIGURE C- 5




FIGURE C- 6





FIGURE C- 7



APPENDIX D

TABULATED EXPERIMENTAL DATA

TABLE D- 1 (DISPLACEMENT DATA)

RUN-201

DC200(500)CS

K= 15.40 DARCY

Q= 2.5 CC/HR

SWI= 9.80 PER CENT

TEMP= 22.0 C

KOI= 13.35 DARCY

IOIP= 675.6 CC

PORF VOL.= 749.0 CC

| DATE | TIME (HRS) | PRFSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|--------------------------|-------|--------------|
| 3101 | 16.30 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.098 |
| 102 | 23.00 | 1.64 | 0.022 | 17.1 | 0.0 | 1.01 | 0.00 | 0.120 |
| 202 | 8.45 | 1.81 | 0.055 | 20.9 | 0.0 | 4.10 | 0.00 | 0.153 |
| 202 | 22.30 | 1.39 | 0.101 | 37.5 | 0.0 | 9.65 | 0.00 | 0.199 |
| 302 | 23.00 | 0.79 | 0.182 | 60.0 | 0.0 | 18.53 | 0.00 | 0.280 |
| 402 | 8.50 | 0.59 | 0.262 | 58.7 | 0.0 | 27.22 | 0.00 | 0.360 |
| 502 | 10.00 | 0.25 | 0.300 | 20.3 | 8.2 | 30.22 | 0.40 | 0.387 |
| 602 | 14.00 | 0.19 | 0.392 | 17.3 | 53.2 | 32.78 | 3.07 | 0.408 |
| 702 | 8.45 | 0.16 | 0.455 | 7.1 | 39.9 | 33.83 | 5.61 | 0.417 |
| 702 | 23.15 | 0.08 | 0.503 | 4.6 | 32.6 | 34.51 | 7.08 | 0.422 |
| 802 | 17.00 | 0.06 | 0.575 | 5.5 | 40.5 | 35.33 | 7.36 | 0.440 |
| 902 | 12.00 | 0.06 | 0.638 | 5.2 | 41.0 | 36.10 | 7.88 | 0.448 |
| 902 | 20.30 | 0.04 | 0.666 | 1.9 | 19.1 | 36.38 | 10.05 | 0.451 |
| 1002 | 13.30 | 0.02 | 0.723 | 2.9 | 39.9 | 36.81 | 13.75 | 0.454 |
| 1102 | 8.40 | 0.02 | 0.787 | 4.0 | 43.0 | 37.40 | 10.75 | 0.461 |
| 1102 | 23.00 | 0.02 | 0.834 | 2.5 | 36.8 | 37.77 | 14.72 | 0.459 |
| 1202 | 18.45 | 0.02 | 0.895 | 2.8 | 39.0 | 38.18 | 13.92 | 0.468 |
| 1302 | 13.10 | 0.02 | 0.957 | 3.0 | 42.5 | 38.63 | 14.16 | 0.473 |
| 1402 | 22.00 | 0.02 | 1.066 | 4.5 | 78.5 | 39.29 | 17.44 | 0.478 |
| 1502 | 15.50 | 0.02 | 1.126 | 2.5 | 44.5 | 39.66 | 17.80 | 0.478 |
| 1602 | 10.30 | 0.02 | 1.189 | 2.4 | 42.6 | 40.02 | 17.75 | 0.484 |
| 1702 | 13.45 | 0.02 | 1.250 | 1.9 | 42.1 | 40.30 | 22.15 | 0.489 |
| 1802 | 23.00 | 0.02 | 1.361 | 3.7 | 78.1 | 40.85 | 21.10 | 0.496 |
| 1902 | 11.30 | 0.02 | 1.403 | 1.5 | 28.5 | 41.07 | 19.00 | 0.499 |
| 2002 | 13.15 | 0.02 | 1.489 | 2.7 | 62.3 | 41.47 | 23.07 | 0.503 |
| 2102 | 12.30 | 0.02 | 1.567 | 1.8 | 57.9 | 41.74 | 32.16 | 0.503 |
| 2202 | 13.30 | 0.02 | 1.650 | 2.5 | 58.3 | 42.11 | 23.32 | 0.508 |
| 2302 | 8.45 | 0.01 | 1.714 | 1.0 | 43.0 | 42.25 | 43.00 | 0.515 |
| 2402 | 8.40 | 0.01 | 1.794 | 1.6 | 58.4 | 42.49 | 36.50 | 0.517 |
| 2402 | 22.00 | 0.01 | 1.839 | 2.1 | 33.2 | 42.80 | 15.80 | 0.518 |
| 2602 | 18.15 | 0.01 | 1.986 | 3.1 | 105.0 | 43.26 | 33.87 | 0.525 |
| 2702 | 14.00 | 0.01 | 2.053 | 1.6 | 47.1 | 43.50 | 29.43 | 0.528 |
| 203 | 13.30 | 0.01 | 2.290 | 4.5 | 174.2 | 44.16 | 38.71 | 0.534 |
| 303 | 8.20 | 0.01 | 2.393 | 1.7 | 75.5 | 44.41 | 44.41 | 0.536 |
| 403 | 14.45 | 0.01 | 2.455 | 1.4 | 45.1 | 44.62 | 32.21 | 0.537 |

TABLE D- 2 (DISPLACEMENT DATA)

RUN-202

DC200(500)CS

K= 17.34 DARCY

Q= 10.0 CC/HR

SWI=11.26 PER CENT

TEMP= 21.0 C

KOI= 13.55 DARCY

IOIP= 677.0 CC

PORE VOL.= 770.4 CC

| DATE | TIME (HRS) | PRFSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|--------------------------|--------|--------------|
| 1004 | 21.00 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.112 |
| 1004 | 23.30 | 6.80 | 0.020 | 16.0 | 0.0 | 0.84 | 0.00 | 0.133 |
| 1104 | 7.00 | 5.10 | 0.121 | 77.5 | 0.0 | 12.29 | 0.00 | 0.233 |
| 1104 | 9.10 | 4.20 | 0.151 | 23.6 | 0.0 | 15.77 | 0.00 | 0.264 |
| 1104 | 11.10 | 3.20 | 0.179 | 20.9 | 0.0 | 18.86 | 0.00 | 0.291 |
| 1104 | 13.30 | 2.00 | 0.227 | 37.6 | 0.0 | 24.41 | 0.00 | 0.340 |
| 1104 | 19.05 | 1.30 | 0.282 | 12.5 | 31.5 | 26.26 | 2.52 | 0.354 |
| 1104 | 23.00 | 1.20 | 0.336 | 9.5 | 31.0 | 27.66 | 3.26 | 0.367 |
| 1204 | 9.10 | 1.00 | 0.471 | 12.3 | 92.0 | 29.48 | 7.47 | 0.383 |
| 1204 | 16.30 | 0.90 | 0.567 | 9.1 | 68.8 | 30.82 | 7.56 | 0.390 |
| 1204 | 23.25 | 0.80 | 0.660 | 6.2 | 64.5 | 31.74 | 10.40 | 0.399 |
| 1304 | 23.00 | 0.70 | 0.976 | 15.9 | 223.0 | 34.09 | 14.02 | 0.425 |
| 1404 | 8.30 | 0.60 | 1.099 | 5.0 | 89.0 | 34.83 | 17.80 | 0.433 |
| 1404 | 20.40 | 0.60 | 1.262 | 6.0 | 121.0 | 35.71 | 20.16 | 0.439 |
| 1504 | 23.00 | 0.60 | 1.615 | 9.6 | 260.5 | 37.13 | 27.13 | 0.454 |
| 1604 | 20.50 | 0.50 | 1.902 | 6.0 | 214.0 | 38.02 | 35.66 | 0.463 |
| 1704 | 21.10 | 0.50 | 2.227 | 3.8 | 244.5 | 38.58 | 64.34 | 0.471 |
| 1804 | 19.45 | 0.50 | 2.527 | 6.0 | 225.0 | 39.46 | 37.50 | 0.478 |
| 1904 | 17.00 | 0.50 | 2.811 | 3.2 | 215.0 | 39.94 | 67.18 | 0.484 |
| 2004 | 18.15 | 0.40 | 3.146 | 4.2 | 253.5 | 40.56 | 60.35 | 0.489 |
| 2104 | 22.10 | 0.40 | 3.516 | 5.5 | 279.5 | 41.37 | 50.81 | 0.497 |
| 2204 | 21.00 | 0.40 | 3.822 | 4.5 | 229.5 | 42.03 | 51.00 | 0.505 |
| 2304 | 22.30 | 0.40 | 4.157 | 2.5 | 250.5 | 42.40 | 100.20 | 0.515 |
| 2504 | 20.45 | 0.30 | 4.747 | 6.0 | 451.0 | 43.29 | 75.16 | 0.520 |
| 2604 | 21.00 | 0.30 | 5.074 | 4.0 | 248.0 | 43.88 | 62.00 | 0.525 |
| 2704 | 22.45 | 0.30 | 5.407 | 4.0 | 249.0 | 44.47 | 62.25 | 0.534 |
| 2804 | 22.15 | 0.30 | 5.719 | 2.5 | 237.0 | 44.84 | 94.80 | 0.539 |
| 3004 | 21.10 | 0.30 | 6.344 | 5.0 | 473.0 | 45.58 | 94.60 | 0.550 |
| 105 | 22.40 | 0.30 | 6.683 | 2.0 | 259.0 | 45.87 | 129.50 | 0.552 |
| 205 | 21.00 | 0.30 | 6.978 | 1.0 | 227.0 | 46.02 | 227.00 | 0.554 |
| 305 | 14.00 | 0.30 | 7.206 | 0.5 | 174.5 | 46.10 | 349.00 | 0.554 |

TABLE D- 3 (DISPLACEMENT DATA)

RUN-203

DC200(500)CS

K= 16.39 DARCY

Q= 160.0 CC/HR

SWI=11.45 PER CENT

TEMP= 21.0 C

KOI= 14.31 DARCY

IOIP= 666.2 CC

PORE VOL.= 752.4 CC

| DATE | TIME (HRS) | PRFSS DRNP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|--------------------------|-------|--------------|
| 2405 | 22.00 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.114 |
| 2405 | 22.10 | 125.00 | 0.070 | 48.0 | 0.0 | 5.66 | 0.00 | 0.149 |
| 2405 | 22.25 | 107.20 | 0.134 | 40.0 | 0.0 | 11.66 | 0.00 | 0.204 |
| 2405 | 22.37 | 79.60 | 0.199 | 46.5 | 0.0 | 18.64 | 0.00 | 0.253 |
| 2405 | 22.56 | 47.60 | 0.208 | 7.3 | 0.0 | 19.74 | 0.00 | 0.323 |
| 2405 | 23.30 | 21.50 | 0.331 | 45.5 | 52.4 | 26.57 | 1.15 | 0.376 |
| 2505 | 0.01 | 15.20 | 0.448 | 15.1 | 72.0 | 28.83 | 4.76 | 0.397 |
| 2505 | 0.33 | 12.60 | 0.559 | 9.4 | 76.5 | 30.24 | 8.13 | 0.406 |
| 2505 | 1.39 | 9.20 | 0.793 | 12.5 | 165.3 | 32.12 | 13.22 | 0.420 |
| 2505 | 3.48 | 6.10 | 1.251 | 21.8 | 327.8 | 35.39 | 15.03 | 0.443 |
| 2505 | 6.23 | 5.40 | 1.819 | 19.0 | 412.0 | 38.24 | 21.68 | 0.463 |
| 2505 | 7.30 | 5.20 | 2.043 | 5.3 | 162.0 | 39.04 | 30.56 | 0.473 |
| 2505 | 8.33 | 4.60 | 2.269 | 6.2 | 169.7 | 39.97 | 27.37 | 0.473 |
| 2505 | 9.36 | 4.40 | 2.497 | 4.9 | 168.8 | 40.70 | 34.44 | 0.476 |
| 2505 | 11.25 | 3.90 | 2.910 | 7.7 | 312.8 | 41.86 | 40.62 | 0.474 |
| 2505 | 13.51 | 3.50 | 3.415 | 8.0 | 371.0 | 43.06 | 46.37 | 0.486 |
| 2505 | 15.55 | 3.30 | 3.869 | 5.0 | 339.7 | 43.81 | 67.93 | 0.488 |

TABLE D- 4 (DISPLACEMENT DATA)

RUN-204

DC200(500)CS

K= 13.75 DARCY

Q= 300.0 CC/HR

SWI=12.50 PER CENT

TEMP= 21.0 C

KOI= 12.12 DARCY

IOIP= 680.9 CC

PORE VOL.= 778.0 CC

| DATE | TIME (HRS) | PRFSS DRDP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|--------------------------|-------|--------------|
| 1506 | 19.50 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.125 |
| 1506 | 19.57 | 269.00 | 0.048 | 36.0 | 0.0 | 3.77 | 0.00 | 0.173 |
| 1506 | 20.00 | 242.00 | 0.074 | 16.0 | 0.1 | 6.12 | 0.00 | 0.199 |
| 1506 | 20.05 | 200.00 | 0.107 | 23.0 | 0.3 | 9.50 | 0.01 | 0.232 |
| 1506 | 20.10 | 160.00 | 0.138 | 22.0 | 0.4 | 12.73 | 0.01 | 0.262 |
| 1506 | 20.17 | 108.00 | 0.179 | 28.9 | 0.5 | 16.98 | 0.01 | 0.303 |
| 1506 | 20.27 | 70.00 | 0.246 | 32.0 | 21.0 | 21.68 | 0.65 | 0.343 |
| 1506 | 20.38 | 49.60 | 0.312 | 20.5 | 32.5 | 24.69 | 1.58 | 0.366 |
| 1506 | 20.45 | 41.50 | 0.363 | 9.0 | 32.0 | 26.01 | 3.55 | 0.377 |
| 1506 | 21.00 | 32.50 | 0.472 | 12.7 | 72.8 | 27.87 | 5.73 | 0.392 |
| 1506 | 21.20 | 26.60 | 0.595 | 10.6 | 85.9 | 29.43 | 8.10 | 0.404 |
| 1506 | 21.36 | 23.20 | 0.704 | 8.1 | 76.4 | 30.62 | 9.43 | 0.416 |
| 1506 | 21.54 | 20.60 | 0.817 | 6.4 | 81.6 | 31.56 | 12.75 | 0.423 |
| 1506 | 22.10 | 18.70 | 0.915 | 7.0 | 83.1 | 32.59 | 11.87 | 0.414 |
| 1506 | 22.28 | 17.20 | 1.046 | 6.4 | 86.5 | 33.53 | 13.51 | 0.434 |
| 1506 | 22.45 | 15.80 | 1.159 | 5.5 | 84.0 | 34.33 | 15.27 | 0.439 |
| 1506 | 23.20 | 14.00 | 1.390 | 8.0 | 172.7 | 35.51 | 21.58 | 0.449 |
| 1506 | 23.37 | 13.10 | 1.503 | 3.4 | 85.7 | 36.01 | 25.20 | 0.452 |
| 1606 | 0.14 | 11.80 | 1.736 | 6.6 | 186.6 | 36.98 | 28.27 | 0.444 |
| 1606 | 0.33 | 11.40 | 1.871 | 2.5 | 93.9 | 37.34 | 37.56 | 0.459 |
| 1606 | 1.10 | 10.30 | 2.118 | 4.8 | 186.2 | 38.05 | 38.79 | 0.466 |
| 1606 | 1.28 | 10.00 | 2.233 | 2.7 | 88.1 | 38.44 | 32.62 | 0.469 |
| 1606 | 2.06 | 9.30 | 2.361 | 2.3 | 97.4 | 38.78 | 42.34 | 0.471 |
| 1606 | 2.23 | 9.00 | 2.473 | 2.5 | 85.6 | 39.15 | 34.24 | 0.473 |
| 1606 | 2.41 | 8.70 | 2.588 | 2.0 | 89.0 | 39.44 | 44.50 | 0.474 |
| 1606 | 3.00 | 8.50 | 2.712 | 2.0 | 93.3 | 39.74 | 46.65 | 0.478 |
| 1606 | 3.36 | 8.00 | 2.953 | 3.1 | 188.1 | 40.19 | 60.67 | 0.477 |
| 1606 | 3.55 | 7.70 | 3.089 | 2.4 | 97.6 | 40.54 | 40.66 | 0.488 |
| 1606 | 4.12 | 7.60 | 3.194 | 1.8 | 85.2 | 40.81 | 47.33 | 0.483 |
| 1606 | 4.48 | 7.20 | 3.428 | 2.4 | 181.0 | 41.16 | 75.41 | 0.485 |
| 1606 | 5.06 | 7.00 | 3.530 | 1.7 | 90.1 | 41.41 | 53.00 | 0.470 |
| 1606 | 5.24 | 6.90 | 3.666 | 1.5 | 90.0 | 41.63 | 60.00 | 0.491 |

TABLE D- 5 (DISPLACEMENT DATA)

RUN-205

DC200(500)CS

Q= 800.0 CC/HR

SWI=11.44 PER CENT

K= 8.43 DARCY

TEMP= 22.0 C

KOI= 7.30 DARCY

IOIP= 665.1 CC

PORE VOL.= 751.0 CC

| DATE | TIME (HRS) | PRF SS DRIP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|-------------------------|----------------------|---------------------|-----------------------|--------------------------|-------|--------------|
| 2806 | 8.24 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.114 |
| 2806 | 8.29 | 1065.00 | 0.089 | 42.6 | 0.4 | 4.86 | 0.00 | 0.203 |
| 2806 | 8.34 | 470.00 | 0.177 | 42.2 | 3.8 | 11.20 | 0.09 | 0.285 |
| 2806 | 8.37 | 310.00 | 0.238 | 23.5 | 4.8 | 14.73 | 0.20 | 0.340 |
| 2806 | 8.42 | 225.00 | 0.320 | 20.6 | 45.0 | 17.83 | 2.18 | 0.363 |
| 2806 | 8.49 | 160.00 | 0.443 | 26.0 | 62.0 | 21.74 | 2.38 | 0.403 |
| 2806 | 9.02 | 111.20 | 0.683 | 29.4 | 157.7 | 26.16 | 5.36 | 0.432 |
| 2806 | 9.15 | 84.50 | 0.928 | 20.0 | 172.0 | 29.17 | 8.60 | 0.448 |
| 2806 | 9.29 | 70.00 | 1.183 | 18.3 | 180.7 | 31.92 | 9.87 | 0.463 |
| 2806 | 9.49 | 60.40 | 1.436 | 10.3 | 180.1 | 33.47 | 17.48 | 0.477 |
| 2806 | 10.02 | 54.20 | 1.679 | 9.3 | 180.3 | 34.87 | 19.38 | 0.479 |
| 2806 | 10.16 | 49.20 | 1.929 | 9.9 | 183.3 | 36.35 | 18.51 | 0.485 |
| 2806 | 10.29 | 45.10 | 2.174 | 8.1 | 175.9 | 37.57 | 21.71 | 0.496 |
| 2806 | 10.44 | 41.50 | 2.445 | 10.0 | 194.0 | 39.08 | 19.40 | 0.509 |
| 2806 | 10.59 | 39.50 | 2.655 | 5.1 | 150.2 | 39.84 | 29.45 | 0.519 |
| 2806 | 11.21 | 36.80 | 2.963 | 8.0 | 222.0 | 41.05 | 27.75 | 0.531 |
| 2806 | 11.36 | 34.70 | 3.226 | 6.5 | 177.2 | 42.02 | 27.26 | 0.558 |
| 2806 | 11.50 | 33.00 | 3.487 | 5.2 | 195.8 | 42.80 | 37.65 | 0.559 |
| 2806 | 12.04 | 31.40 | 3.740 | 4.0 | 186.0 | 43.41 | 46.50 | 0.564 |
| 2806 | 12.17 | 30.20 | 3.984 | 6.0 | 182.0 | 44.31 | 30.33 | 0.566 |

TABLE D- 6 (DISPLACEMENT DATA)

RUN-206

DC200(500)CS

Q= 20.0 CC/HR

SWI=10.58 PER CENT

K= 7.56 DARCY

TEMP= 22.0 C

KOI= 6.66 DARCY

IOIP= 665.5 CC

PORE VOL.= 744.3 CC

| DATE | TIME (HRS) | PRFSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|--------------------------|-------|--------------|
| 707 | 13.00 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.105 |
| 707 | 13.52 | 35.40 | 0.022 | 14.4 | 0.0 | 0.62 | 0.00 | 0.128 |
| 707 | 14.18 | 34.00 | 0.034 | 7.9 | 0.0 | 1.80 | 0.00 | 0.140 |
| 707 | 15.00 | 31.60 | 0.054 | 12.1 | 0.0 | 3.62 | 0.00 | 0.159 |
| 707 | 15.50 | 28.80 | 0.076 | 17.1 | 0.0 | 6.19 | 0.00 | 0.182 |
| 707 | 16.53 | 25.20 | 0.105 | 23.0 | 0.0 | 9.65 | 0.00 | 0.211 |
| 707 | 19.11 | 17.70 | 0.169 | 47.2 | 0.0 | 16.74 | 0.00 | 0.274 |
| 707 | 21.14 | 10.30 | 0.225 | 44.0 | 0.0 | 23.35 | 0.00 | 0.331 |
| 707 | 22.01 | 8.20 | 0.246 | 16.7 | 0.2 | 25.87 | 0.01 | 0.352 |
| 707 | 23.02 | 6.50 | 0.275 | 1.4 | 10.6 | 26.08 | 7.57 | 0.366 |
| 807 | 7.41 | 3.80 | 0.512 | 45.0 | 133.0 | 32.84 | 2.95 | 0.425 |
| 807 | 10.11 | 3.40 | 0.582 | 5.3 | 47.7 | 33.64 | 9.00 | 0.431 |
| 807 | 12.25 | 3.20 | 0.644 | 4.7 | 42.2 | 34.34 | 8.97 | 0.436 |
| 807 | 21.03 | 2.80 | 0.878 | 14.1 | 165.4 | 36.46 | 11.73 | 0.447 |
| 907 | 5.04 | 2.30 | 1.102 | 11.0 | 155.0 | 38.11 | 14.09 | 0.464 |
| 907 | 13.10 | 2.00 | 1.321 | 9.4 | 158.3 | 39.53 | 16.84 | 0.470 |
| 907 | 21.15 | 1.80 | 1.540 | 8.2 | 157.1 | 40.76 | 19.15 | 0.478 |
| 1007 | 5.23 | 1.70 | 1.762 | 6.3 | 158.8 | 41.70 | 25.20 | 0.486 |
| 1007 | 13.23 | 1.60 | 1.984 | 5.9 | 161.0 | 42.59 | 27.28 | 0.491 |
| 1107 | 9.35 | 1.50 | 2.540 | 14.6 | 406.1 | 44.78 | 27.81 | 0.502 |
| 1107 | 15.30 | 1.50 | 2.678 | 2.4 | 102.9 | 45.14 | 42.87 | 0.502 |
| 1207 | 10.15 | 1.20 | 3.191 | 11.4 | 377.6 | 46.86 | 33.12 | 0.508 |
| 1207 | 20.45 | 1.10 | 3.484 | 4.4 | 210.0 | 47.52 | 47.72 | 0.519 |

TABLE D- 7 (DISPLACEMENT DATA)

RUN-207

DC200(500)CS

Q= 560.0 CC/HR

SWI=11.86 PER CENT

K= 8.54 DARCY

TEMP= 21.0 C

KOI= 8.18 DARCY

IOIP= 674.6 CC

PORE VOL.= 765.4 CC

| DATE | TIME (HRS) | PRFSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|--------------------------|-------|--------------|
| 1007 | 12.43 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.118 |
| 1007 | 12.48 | 660.00 | 0.052 | 30.0 | 0.0 | 3.21 | 0.00 | 0.170 |
| 1007 | 12.49 | 675.00 | 0.066 | 7.0 | 0.0 | 4.25 | 0.00 | 0.185 |
| 1007 | 12.54 | 544.00 | 0.118 | 35.0 | 0.0 | 9.44 | 0.00 | 0.237 |
| 1007 | 12.57 | 424.00 | 0.150 | 18.0 | 0.0 | 12.11 | 0.00 | 0.268 |
| 1007 | 13.00 | 290.00 | 0.188 | 27.4 | 3.2 | 16.17 | 0.11 | 0.302 |
| 1007 | 13.09 | 158.00 | 0.303 | 42.4 | 49.6 | 22.46 | 1.16 | 0.352 |
| 1007 | 13.19 | 110.00 | 0.423 | 23.3 | 69.5 | 25.91 | 2.98 | 0.382 |
| 1007 | 13.30 | 86.40 | 0.551 | 16.2 | 74.4 | 28.32 | 4.59 | 0.412 |
| 1007 | 13.40 | 72.20 | 0.677 | 11.0 | 79.7 | 29.95 | 7.24 | 0.434 |
| 1007 | 13.50 | 62.50 | 0.794 | 10.1 | 81.1 | 31.44 | 8.02 | 0.446 |
| 1007 | 14.00 | 56.00 | 0.916 | 8.3 | 85.7 | 32.67 | 10.32 | 0.455 |
| 1007 | 14.09 | 50.60 | 1.036 | 7.7 | 86.3 | 33.82 | 11.20 | 0.463 |
| 1007 | 14.20 | 46.40 | 1.158 | 5.7 | 88.3 | 34.66 | 15.49 | 0.469 |
| 1007 | 14.30 | 42.50 | 1.283 | 6.6 | 91.4 | 35.64 | 13.84 | 0.475 |
| 1007 | 14.40 | 40.00 | 1.406 | 4.2 | 88.8 | 36.26 | 21.14 | 0.482 |
| 1007 | 14.49 | 38.00 | 1.520 | 4.4 | 83.6 | 36.91 | 19.00 | 0.486 |
| 1007 | 15.10 | 33.80 | 1.770 | 9.2 | 185.0 | 38.28 | 20.10 | 0.495 |
| 1007 | 15.30 | 30.40 | 2.013 | 6.9 | 182.8 | 39.30 | 26.49 | 0.499 |
| 1007 | 15.50 | 28.40 | 2.252 | 6.4 | 179.0 | 40.25 | 27.96 | 0.504 |
| 1007 | 16.09 | 26.80 | 2.482 | 6.5 | 171.6 | 41.21 | 26.40 | 0.510 |
| 1007 | 16.30 | 24.60 | 2.736 | 4.5 | 190.6 | 41.88 | 42.35 | 0.516 |
| 1007 | 16.49 | 23.20 | 2.974 | 4.4 | 180.4 | 42.53 | 41.00 | 0.518 |
| 1007 | 17.09 | 22.10 | 3.220 | 4.6 | 185.3 | 43.21 | 40.28 | 0.521 |
| 1007 | 17.30 | 21.00 | 3.458 | 4.4 | 180.4 | 43.87 | 41.00 | 0.524 |
| 1007 | 17.50 | 20.20 | 3.699 | 3.0 | 181.7 | 44.31 | 60.56 | 0.527 |
| 1007 | 18.09 | 19.40 | 3.926 | 4.2 | 179.2 | 44.93 | 42.66 | 0.520 |

TABLE D- 8 (DISPLACEMENT DATA)

RUN-208

DC200(.500)CS

K= 16.72 DARCY

Q= 50.0 CC/HR

SWI=12.46 PER CENT

TEMP= 21.0 C

KOI= 14.95 DARCY

IOIP= 688.0 CC

PORE VOL.= 785.9 CC

| DATE | TIME (HRS) | PRFSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 1307 | 11.50 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.124 |
| 1307 | 12.20 | 35.90 | 0.033 | 20.0 | 0.0 | 1.56 | 0.00 | 0.157 |
| 1307 | 12.56 | 31.10 | 0.068 | 21.0 | 0.0 | 4.62 | 0.00 | 0.193 |
| 1307 | 13.22 | 27.00 | 0.111 | 33.0 | 0.0 | 9.41 | 0.00 | 0.236 |
| 1307 | 13.41 | 22.80 | 0.132 | 11.1 | 0.0 | 11.03 | 0.00 | 0.256 |
| 1307 | 14.57 | 12.00 | 0.213 | 67.9 | 0.1 | 20.90 | 0.00 | 0.338 |
| 1307 | 15.40 | 10.50 | 0.251 | 19.3 | 9.7 | 23.70 | 0.50 | 0.364 |
| 1307 | 16.20 | 8.30 | 0.309 | 21.2 | 23.8 | 26.78 | 1.12 | 0.391 |
| 1307 | 17.00 | 6.80 | 0.366 | 14.2 | 30.5 | 28.85 | 2.14 | 0.409 |
| 1307 | 17.40 | 5.50 | 0.422 | 9.4 | 34.6 | 30.21 | 3.68 | 0.421 |
| 1307 | 18.30 | 4.90 | 0.468 | 7.0 | 37.0 | 31.23 | 5.28 | 0.420 |
| 1307 | 19.40 | 4.00 | 0.524 | 6.2 | 37.8 | 32.13 | 6.09 | 0.428 |
| 1307 | 20.34 | 3.40 | 0.580 | 5.1 | 39.1 | 32.87 | 7.66 | 0.434 |
| 1307 | 21.27 | 3.20 | 0.636 | 3.8 | 39.8 | 33.43 | 10.47 | 0.439 |
| 1407 | 0.30 | 3.00 | 0.843 | 13.3 | 155.0 | 35.36 | 11.65 | 0.449 |
| 1407 | 3.45 | 2.60 | 1.066 | 12.0 | 164.2 | 37.10 | 13.68 | 0.463 |
| 1407 | 7.20 | 2.10 | 1.278 | 8.6 | 159.1 | 38.35 | 18.50 | 0.473 |
| 1407 | 10.50 | 2.00 | 1.501 | 7.0 | 168.8 | 39.37 | 24.11 | 0.481 |
| 1407 | 13.20 | 1.80 | 1.665 | 5.9 | 125.2 | 40.23 | 21.22 | 0.486 |
| 1407 | 16.45 | 1.60 | 1.884 | 7.4 | 168.8 | 41.30 | 22.81 | 0.490 |
| 1407 | 20.16 | 1.60 | 2.108 | 5.9 | 170.1 | 42.16 | 28.83 | 0.497 |
| 1407 | 21.55 | 1.50 | 2.222 | 2.4 | 90.6 | 42.51 | 37.75 | 0.497 |
| 1507 | 0.31 | 1.50 | 2.451 | 3.8 | 182.0 | 43.06 | 47.89 | 0.494 |
| 1507 | 3.59 | 1.40 | 2.673 | 3.8 | 171.0 | 43.61 | 45.00 | 0.498 |
| 1507 | 7.00 | 1.30 | 2.864 | 3.3 | 152.7 | 44.09 | 46.27 | 0.494 |
| 1507 | 10.21 | 1.30 | 3.028 | 2.6 | 121.9 | 44.47 | 46.88 | 0.504 |
| 1507 | 15.10 | 1.20 | 3.343 | 3.8 | 250.2 | 45.02 | 65.84 | 0.500 |

TABLE D- 9 (DISPLACEMENT DATA)

RUN-209

DC200(500)CS

Q= 15.0 CC/HR

SWI= 9.70 PER CENT

K= 8.66 DARCY

TEMP= 22.0 C

KOI= 8.18 DARCY

IOIP= 648.8 CC

PORE VOL.= 718.4 CC

| DATE | TIME (HRS) | PRFSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 2007 | 23.18 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.097 |
| 2107 | 3.38 | 15.10 | 0.092 | 59.1 | 0.1 | 7.54 | 0.00 | 0.189 |
| 2107 | 6.58 | 10.10 | 0.162 | 50.0 | 0.0 | 15.25 | 0.00 | 0.258 |
| 2107 | 10.00 | 6.20 | 0.228 | 55.3 | 1.0 | 23.77 | 0.01 | 0.324 |
| 2107 | 12.18 | 4.20 | 0.278 | 17.5 | 19.5 | 26.47 | 1.11 | 0.346 |
| 2107 | 15.05 | 3.60 | 0.337 | 8.1 | 36.7 | 27.72 | 4.53 | 0.354 |
| 2107 | 20.55 | 2.80 | 0.462 | 13.1 | 77.7 | 29.73 | 5.93 | 0.371 |
| 2207 | 10.39 | 2.20 | 0.699 | 18.0 | 158.5 | 32.51 | 8.80 | 0.387 |
| 2207 | 21.58 | 1.90 | 0.911 | 14.0 | 159.8 | 34.67 | 11.41 | 0.378 |
| 2307 | 12.55 | 1.60 | 1.255 | 32.2 | 223.2 | 39.63 | 6.93 | 0.411 |
| 2307 | 23.08 | 1.40 | 1.477 | 8.0 | 152.4 | 40.86 | 19.05 | 0.420 |
| 2407 | 12.08 | 1.30 | 1.755 | 8.9 | 200.1 | 42.23 | 22.48 | 0.420 |
| 2507 | 0.46 | 1.20 | 2.027 | 8.1 | 191.5 | 43.48 | 23.64 | 0.425 |
| 2507 | 8.30 | 1.15 | 2.330 | 3.5 | 116.9 | 44.02 | 33.40 | 0.566 |
| 2507 | 21.25 | 1.10 | 2.607 | 5.4 | 198.0 | 44.85 | 36.66 | 0.567 |
| 2607 | 11.30 | 1.00 | 2.863 | 4.5 | 181.9 | 45.55 | 40.42 | 0.570 |

TABLE D-10 (DISPLACEMENT DATA)

RUN-210

WAINWRIGHT(1080)CS

Q= 15.0 CC/HR

SWI= 8.31 PER CENT

K= 12.45 DARCY

TEMP= 22.2 C

KOI= 10.39 DARCY

IOIP= 682.9 CC

PORE VOL.= 744.8 CC

| DATE | TIME (HRS) | PRFESS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|-------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 2807 | 11.15 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.083 |
| 2807 | 12.15 | 23.80 | 0.020 | 12.7 | 0.0 | 0.42 | 0.00 | 0.103 |
| 2807 | 14.14 | 15.30 | 0.060 | 25.3 | 0.0 | 4.12 | 0.00 | 0.143 |
| 2807 | 17.00 | 5.30 | 0.107 | 30.0 | 6.0 | 8.52 | 0.20 | 0.182 |
| 2807 | 20.00 | 5.20 | 0.176 | 19.0 | 36.6 | 11.30 | 1.92 | 0.202 |
| 2907 | 3.45 | 3.90 | 0.334 | 39.5 | 78.3 | 17.08 | 1.98 | 0.255 |
| 2907 | 10.55 | 3.60 | 0.469 | 21.4 | 94.4 | 20.22 | 4.41 | 0.263 |
| 2907 | 17.30 | 3.00 | 0.604 | 16.7 | 88.1 | 22.66 | 5.27 | 0.279 |
| 3007 | 1.45 | 2.80 | 0.771 | 19.3 | 104.7 | 25.49 | 5.42 | 0.307 |
| 3007 | 9.42 | 2.60 | 0.931 | 13.6 | 110.0 | 27.48 | 8.08 | 0.319 |
| 3007 | 17.45 | 2.20 | 1.099 | 14.1 | 112.4 | 29.55 | 7.97 | 0.336 |
| 3107 | 1.58 | 2.10 | 1.264 | 11.0 | 112.0 | 31.16 | 10.18 | 0.350 |
| 3107 | 14.00 | 2.00 | 1.491 | 14.4 | 161.7 | 33.26 | 11.22 | 0.360 |
| 3107 | 21.45 | 1.90 | 1.659 | 10.6 | 11.3 | 34.82 | 1.07 | 0.513 |
| 108 | 14.12 | 1.80 | 1.987 | 18.4 | 229.5 | 37.51 | 12.47 | 0.532 |
| 208 | 10.43 | 1.70 | 2.401 | 19.7 | 296.2 | 40.40 | 15.03 | 0.549 |
| 208 | 20.00 | 1.60 | 2.605 | 8.5 | 149.1 | 41.64 | 17.54 | 0.553 |
| 308 | 10.50 | 1.60 | 2.886 | 9.3 | 204.1 | 43.00 | 21.94 | 0.560 |
| 308 | 20.10 | 1.50 | 3.074 | 7.4 | 132.5 | 44.09 | 17.90 | 0.570 |

TABLE D-11 (DISPLACEMENT DATA)

RUN-211

WAINWRIGHT(1080)CS

Q= 25.0 CC/HR

SWI= 9.68 PER CENT

K= 12.64 DARCY

TEMP= 22.2 C

KOI= 10.41 DARCY

IOIP= 679.8 CC

PORE VOL.= 752.6 CC

| DATE | TIME (HRS) | PR FSS DRNP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|-------------------------|----------------------|---------------------|-----------------------|--------------------------|-------|--------------|
| 3007 | 11.10 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.096 |
| 3007 | 11.49 | 38.20 | 0.022 | 11.5 | 0.0 | 0.25 | 0.00 | 0.119 |
| 3007 | 12.02 | 35.00 | 0.030 | 3.9 | 0.0 | 0.82 | 0.00 | 0.127 |
| 3007 | 14.13 | 10.40 | 0.108 | 52.1 | 3.0 | 8.48 | 0.05 | 0.201 |
| 3007 | 14.43 | 8.80 | 0.134 | 8.8 | 11.2 | 9.78 | 1.27 | 0.212 |
| 3007 | 21.41 | 5.20 | 0.372 | 40.5 | 146.3 | 15.73 | 3.61 | 0.255 |
| 3107 | 2.30 | 4.80 | 0.531 | 18.8 | 104.9 | 18.50 | 5.57 | 0.275 |
| 3107 | 7.30 | 4.50 | 0.697 | 15.0 | 112.4 | 20.71 | 7.49 | 0.292 |
| 3107 | 13.25 | 4.00 | 0.906 | 18.4 | 143.6 | 23.41 | 7.80 | 0.310 |
| 3107 | 21.00 | 3.70 | 1.166 | 22.2 | 181.1 | 26.68 | 8.15 | 0.330 |
| 108 | 13.58 | 3.00 | 1.687 | 42.8 | 407.7 | 32.98 | 9.52 | 0.309 |
| 108 | 20.14 | 2.80 | 1.950 | 16.4 | 152.0 | 35.39 | 9.26 | 0.370 |
| 208 | 10.38 | 2.60 | 2.444 | 31.2 | 354.1 | 39.98 | 11.34 | 0.394 |
| 208 | 21.33 | 2.20 | 2.810 | 25.7 | 267.8 | 43.76 | 10.42 | 0.403 |
| 308 | 10.50 | 2.10 | 3.264 | 14.0 | 339.6 | 45.82 | 24.25 | 0.406 |
| 308 | 20.10 | 2.00 | 3.582 | 11.3 | 237.4 | 47.48 | 21.00 | 0.409 |

TABLE D-12 (DISPLACEMENT DATA)

RUN-212

WAINWRIGHT(1080)CS

Q= 50.0 CC/HR

SWI= 9.93 PER CENT

K= 11.99 DARCYS

TEMP= 22.2 C

KOI= 11.12 DARCYS

IOIP= 678.9 CC

PORE VOL.= 753.7 CC

| DATE | TIME (HRS) | PRFSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 1108 | 13.43 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.099 |
| 1108 | 14.07 | 69.20 | 0.026 | 11.0 | 0.0 | 0.17 | 0.00 | 0.125 |
| 1108 | 14.28 | 59.90 | 0.049 | 18.1 | 0.0 | 2.84 | 0.00 | 0.148 |
| 1108 | 14.45 | 49.90 | 0.068 | 16.2 | 0.0 | 5.22 | 0.00 | 0.168 |
| 1108 | 15.15 | 34.50 | 0.100 | 27.9 | 0.0 | 9.33 | 0.00 | 0.200 |
| 1108 | 15.38 | 22.80 | 0.127 | 22.9 | 0.1 | 12.71 | 0.00 | 0.226 |
| 1108 | 16.21 | 15.40 | 0.173 | 18.4 | 21.1 | 15.42 | 1.14 | 0.244 |
| 1108 | 19.15 | 9.70 | 0.367 | 29.7 | 121.4 | 19.79 | 4.08 | 0.277 |
| 1108 | 23.34 | 8.30 | 0.652 | 26.6 | 195.5 | 23.71 | 7.34 | 0.303 |
| 1208 | 9.40 | 5.40 | 1.328 | 52.0 | 472.1 | 31.37 | 9.07 | 0.352 |
| 1208 | 13.13 | 5.00 | 1.553 | 10.9 | 159.5 | 32.97 | 14.63 | 0.366 |
| 1208 | 16.39 | 4.80 | 1.779 | 11.6 | 163.9 | 34.68 | 14.12 | 0.374 |
| 1208 | 23.22 | 4.60 | 2.224 | 21.3 | 289.5 | 37.82 | 13.59 | 0.436 |

TABLE D-13 (DISPLACEMENT DATA)

RUN-213

WAINWRIGHT(1080)CS

Q= 7.5 CC/HR

SWI= 9.28 PER CENT

K= 10.35 DARCY

TEMP= 21.6 C

KOI= 9.16 DARCY

IOIP= 653.3 CC

PORE VOL.= 720.3 CC

| DATE | TIME (HRS) | PR FSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|-------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 808 | 12.10 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.092 |
| 808 | 16.13 | 13.08 | 0.041 | 20.7 | 0.0 | 3.16 | 0.00 | 0.134 |
| 808 | 19.26 | 4.54 | 0.074 | 30.4 | 0.0 | 7.82 | 0.00 | 0.167 |
| 808 | 21.24 | 2.30 | 0.095 | 4.5 | 8.0 | 8.50 | 1.77 | 0.177 |
| 808 | 23.10 | 2.16 | 0.113 | 9.2 | 10.2 | 9.91 | 1.10 | 0.181 |
| 908 | 12.28 | 2.14 | 0.252 | 20.8 | 85.5 | 13.10 | 4.11 | 0.201 |
| 908 | 17.00 | 2.08 | 0.299 | 5.7 | 30.2 | 13.97 | 5.29 | 0.206 |
| 908 | 23.28 | 2.00 | 0.366 | 7.6 | 41.7 | 15.13 | 5.48 | 0.215 |
| 1008 | 11.00 | 2.11 | 0.487 | 19.2 | 73.9 | 18.07 | 3.84 | 0.233 |
| 1008 | 23.16 | 1.81 | 0.616 | 17.3 | 81.8 | 20.72 | 4.72 | 0.249 |
| 1108 | 13.25 | 1.74 | 0.762 | 17.5 | 95.8 | 23.40 | 5.47 | 0.262 |
| 1108 | 23.30 | 1.64 | 0.866 | 11.3 | 72.3 | 25.13 | 6.39 | 0.265 |
| 1208 | 9.30 | 1.64 | 0.964 | 12.0 | 69.1 | 26.96 | 5.75 | 0.268 |
| 1308 | 14.00 | 1.58 | 1.263 | 29.7 | 198.8 | 31.51 | 6.69 | 0.290 |
| 1308 | 21.55 | 1.56 | 1.349 | 7.4 | 57.3 | 32.64 | 7.74 | 0.297 |
| 1408 | 10.50 | 1.47 | 1.392 | 2.0 | 28.4 | 32.95 | 14.20 | 0.301 |
| 1408 | 16.55 | 1.37 | 1.453 | 7.5 | 42.5 | 34.10 | 5.66 | 0.303 |
| 1408 | 20.40 | 1.33 | 1.495 | 3.7 | 26.5 | 34.66 | 7.16 | 0.308 |

TABLE D-14 (DISPLACEMENT DATA)

RUN-214

WAINWRIGHT(1080)CS

Q= 800.0 CC/HR

SWI= 9.34 PER CENT

K= 8.56 DARCY

TEMP= 22.2 C

KOI= 6.06 DARCY

IOIP= 682.4 CC

PORE VOL.= 752.7 CC

| DATE | TIME (HRS) | PR FSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|-------------------------|----------------------|---------------------|-----------------------|--------------------------|-------|--------------|
| 1408 | 12.08 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.093 |
| 1408 | 12.16 | 1200.00 | 0.154 | 73.2 | 0.0 | 9.29 | 0.00 | 0.247 |
| 1408 | 12.21 | 1100.00 | 0.239 | 70.0 | 0.0 | 19.54 | 0.00 | 0.332 |
| 1408 | 12.30 | 950.00 | 0.398 | 139.6 | 0.0 | 40.00 | 0.00 | 0.491 |
| 1408 | 12.31 | 930.00 | 0.411 | 10.0 | 0.1 | 41.47 | 0.01 | 0.505 |
| 1408 | 12.42 | 535.00 | 0.631 | 43.6 | 135.2 | 47.86 | 3.10 | 0.544 |
| 1408 | 12.52 | 356.00 | 0.807 | 24.8 | 115.0 | 51.49 | 4.63 | 0.568 |
| 1408 | 13.14 | 295.00 | 1.208 | 25.3 | 283.0 | 55.20 | 11.18 | 0.593 |
| 1408 | 14.12 | 275.00 | 1.691 | 14.9 | 256.3 | 57.38 | 17.20 | 0.735 |
| 1408 | 14.33 | 255.00 | 1.935 | 18.5 | 277.0 | 60.09 | 14.97 | 0.612 |
| 1408 | 14.53 | 216.00 | 2.307 | 21.2 | 263.8 | 63.20 | 12.44 | 0.633 |
| 1408 | 15.12 | 194.00 | 2.649 | 11.2 | 252.5 | 64.84 | 22.54 | 0.639 |
| 1408 | 16.04 | 188.00 | 3.115 | 18.2 | 342.1 | 67.51 | 18.79 | 0.651 |
| 1408 | 16.25 | 172.00 | 3.488 | 4.9 | 288.7 | 68.22 | 58.91 | 0.641 |
| 1408 | 16.44 | 162.00 | 3.832 | 5.6 | 262.0 | 69.05 | 46.78 | 0.637 |
| 1408 | 16.51 | 158.00 | 3.974 | 3.4 | 110.6 | 69.54 | 32.52 | 0.632 |

TABLE D-15 (DISPLACEMENT DATA)

RUN-215

WAINWRIGHT(1080)CS

Q= 100.0 CC/HR

SWI= 9.41 PER CENT

K= 8.32 DARCY

TEMP= 23.8 C

KOI= 6.40 DARCY

IOIP= 663.1 CC

PORE VOL.= 732.0 CC

| DATE | TIME (HRS) | PRF SS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|-------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 1807 | 11.05 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.094 |
| 1807 | 11.20 | 290.00 | 0.038 | 18.3 | 0.0 | 1.28 | 0.00 | 0.132 |
| 1807 | 11.31 | 266.00 | 0.065 | 22.5 | 0.0 | 4.67 | 0.00 | 0.159 |
| 1807 | 11.50 | 225.00 | 0.106 | 36.2 | 0.0 | 10.13 | 0.00 | 0.200 |
| 1807 | 12.11 | 173.00 | 0.158 | 41.6 | 0.0 | 16.40 | 0.00 | 0.252 |
| 1807 | 12.31 | 132.00 | 0.204 | 49.1 | 0.5 | 23.81 | 0.01 | 0.298 |
| 1807 | 12.55 | 90.00 | 0.275 | 24.5 | 12.5 | 27.50 | 0.51 | 0.352 |
| 1807 | 13.10 | 55.00 | 0.453 | 39.6 | 104.2 | 33.47 | 2.63 | 0.387 |
| 1807 | 15.36 | 40.00 | 0.636 | 20.4 | 122.6 | 36.55 | 6.00 | 0.403 |
| 1807 | 16.57 | 32.60 | 0.825 | 15.6 | 123.9 | 38.90 | 7.94 | 0.422 |
| 1807 | 20.20 | 25.60 | 1.297 | 28.0 | 329.0 | 43.13 | 11.75 | 0.445 |
| 1807 | 22.42 | 22.60 | 1.617 | 15.1 | 222.7 | 45.40 | 14.74 | 0.461 |
| 1907 | 0.02 | 21.20 | 1.806 | 10.0 | 131.7 | 46.91 | 13.17 | 0.470 |
| 1907 | 4.45 | 20.80 | 2.517 | 24.0 | 493.7 | 50.53 | 20.57 | 0.506 |
| 1907 | 9.52 | 20.20 | 3.168 | 21.0 | 485.7 | 53.70 | 23.12 | 0.494 |
| 1907 | 13.31 | 19.40 | 3.666 | 13.9 | 360.1 | 55.79 | 25.90 | 0.499 |
| 1907 | 16.35 | 18.40 | 4.095 | 11.4 | 313.6 | 57.51 | 27.50 | 0.501 |

TABLE D-16 (DISPLACEMENT DATA)

RUN-216

WAINWRIGHT(1080)CS

Q= 80.0 CC/HR

SWI= 9.10 PER CENT

K= 8.17 DARCY

TEMP= 21.1 C

KOI= 7.02 DARCY

IOIP= 651.6 CC

PORE VOL.= 716.9 CC

| DATE | TIME (HRS) | PR FSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|-------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 2208 | 14.34 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.091 |
| 2208 | 14.53 | 225.50 | 0.034 | 15.3 | 0.0 | 0.84 | 0.00 | 0.125 |
| 2208 | 15.23 | 176.00 | 0.097 | 49.9 | 0.0 | 8.50 | 0.00 | 0.188 |
| 2208 | 16.29 | 84.50 | 0.223 | 99.5 | 1.0 | 23.77 | 0.01 | 0.312 |
| 2208 | 17.09 | 57.20 | 0.298 | 34.4 | 25.6 | 29.05 | 0.74 | 0.352 |
| 2208 | 20.00 | 32.00 | 0.619 | 37.4 | 199.7 | 34.79 | 5.33 | 0.394 |
| 2208 | 22.54 | 24.40 | 0.945 | 21.3 | 217.9 | 38.06 | 10.23 | 0.417 |
| 2308 | 4.30 | 20.00 | 1.594 | 29.5 | 434.4 | 42.58 | 14.72 | 0.459 |
| 2308 | 9.58 | 17.00 | 2.215 | 18.0 | 430.9 | 45.34 | 23.93 | 0.479 |
| 2308 | 14.15 | 16.50 | 2.706 | 12.0 | 338.2 | 47.19 | 28.18 | 0.498 |
| 2308 | 22.00 | 14.00 | 3.587 | 23.6 | 603.8 | 50.81 | 25.58 | 0.538 |
| 2308 | 23.33 | 14.00 | 3.760 | 5.1 | 124.5 | 51.59 | 24.41 | 0.537 |

TABLE D-17 (DISPLACEMENT DATA)

RUN-217

WAINWRIGHT(1080)CS

Q= 200.0 CC/HR

SWI= 7.30 PER CENT

K= 9.42 DARCY

TEMP= 20.0 C

KOI= 7.36 DARCY

IOIP= 692.3 CC

PORE VOL.= 746.7 CC

| DATE | TIME (HRS) | PR FSS DRNP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|-------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 2608 | 10.22 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.072 |
| 2608 | 10.33 | 583.00 | 0.050 | 23.2 | 0.0 | 1.93 | 0.00 | 0.123 |
| 2608 | 10.41 | 559.00 | 0.091 | 21.8 | 0.0 | 5.08 | 0.00 | 0.164 |
| 2608 | 10.50 | 523.00 | 0.128 | 22.0 | 0.0 | 8.26 | 0.00 | 0.201 |
| 2608 | 11.00 | 474.00 | 0.174 | 40.1 | 0.0 | 14.05 | 0.00 | 0.247 |
| 2608 | 11.14 | 424.00 | 0.238 | 52.5 | 0.0 | 21.63 | 0.00 | 0.311 |
| 2608 | 11.27 | 363.00 | 0.294 | 49.7 | 0.0 | 28.81 | 0.00 | 0.367 |
| 2608 | 11.40 | 269.00 | 0.334 | 31.5 | 0.7 | 33.37 | 0.02 | 0.406 |
| 2608 | 12.45 | 175.00 | 0.646 | 76.2 | 156.2 | 44.38 | 2.04 | 0.509 |
| 2608 | 14.00 | 90.00 | 0.991 | 21.5 | 223.8 | 47.48 | 10.40 | 0.554 |
| 2608 | 15.06 | 79.00 | 1.304 | 11.9 | 199.7 | 49.20 | 16.78 | 0.600 |
| 2608 | 16.48 | 64.00 | 1.744 | 13.0 | 322.7 | 51.08 | 24.82 | 0.608 |
| 2608 | 17.47 | 59.00 | 2.020 | 8.3 | 202.3 | 52.28 | 24.37 | 0.613 |
| 2608 | 19.11 | 55.00 | 2.395 | 8.1 | 274.6 | 53.45 | 33.90 | 0.620 |
| 2608 | 20.42 | 52.00 | 2.804 | 9.1 | 305.6 | 54.76 | 33.58 | 0.619 |
| 2608 | 22.01 | 50.00 | 3.164 | 5.4 | 274.9 | 55.54 | 50.90 | 0.611 |
| 2608 | 22.08 | 48.90 | 3.361 | 4.2 | 146.9 | 56.15 | 34.97 | 0.612 |

TABLE D-18 (DISPLACEMENT DATA)

RUN-218

WAINWRIGHT(1080)CS

Q= 400.0 CC/HR

SWI= 7.03 PER CENT

K= 9.66 DARCY

TEMP= 21.1 C

KOI= 9.22 DARCY

IOIP= 672.2 CC

PORE VOL.= 723.0 CC

| DATE | TIME (HRS) | PRFSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|--------------------------|-------|--------------|
| 2908 | 11.00 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.070 |
| 2908 | 11.09 | 943.00 | 0.078 | 34.9 | 0.0 | 3.73 | 0.00 | 0.149 |
| 2908 | 11.14 | 904.00 | 0.124 | 35.0 | 0.0 | 8.94 | 0.00 | 0.194 |
| 2908 | 11.23 | 714.00 | 0.215 | 70.5 | 0.0 | 19.42 | 0.00 | 0.286 |
| 2908 | 11.33 | 595.00 | 0.304 | 68.8 | 0.0 | 29.66 | 0.00 | 0.374 |
| 2908 | 11.34 | 575.00 | 0.315 | 9.3 | 0.1 | 31.04 | 0.01 | 0.385 |
| 2908 | 11.39 | 431.00 | 0.365 | 28.8 | 8.7 | 35.33 | 0.30 | 0.423 |
| 2908 | 12.00 | 333.00 | 0.558 | 50.8 | 89.4 | 42.88 | 1.75 | 0.493 |
| 2908 | 12.20 | 275.00 | 0.748 | 28.9 | 113.4 | 47.18 | 3.92 | 0.525 |
| 2908 | 12.41 | 230.00 | 0.947 | 15.7 | 131.8 | 49.52 | 8.39 | 0.542 |
| 2908 | 13.01 | 203.00 | 1.136 | 11.0 | 130.7 | 51.16 | 11.88 | 0.551 |
| 2908 | 13.21 | 182.00 | 1.322 | 7.9 | 127.4 | 52.33 | 16.12 | 0.560 |
| 2908 | 13.43 | 163.00 | 1.524 | 7.0 | 142.7 | 53.37 | 20.38 | 0.565 |
| 2908 | 14.04 | 147.00 | 1.723 | 5.8 | 141.9 | 54.23 | 24.46 | 0.568 |
| 2908 | 14.25 | 137.00 | 1.910 | 4.2 | 134.1 | 54.86 | 31.92 | 0.569 |
| 2908 | 14.48 | 127.00 | 2.135 | 5.2 | 156.3 | 55.63 | 30.05 | 0.578 |
| 2908 | 15.10 | 118.00 | 2.333 | 4.9 | 153.4 | 56.36 | 31.30 | 0.564 |
| 2908 | 15.33 | 111.00 | 2.562 | 2.6 | 157.3 | 56.75 | 60.50 | 0.576 |
| 2908 | 16.00 | 104.00 | 2.766 | 3.7 | 145.3 | 57.30 | 39.27 | 0.578 |
| 2908 | 16.21 | 99.00 | 3.020 | 3.3 | 157.1 | 57.79 | 47.60 | 0.615 |
| 2908 | 16.45 | 96.00 | 3.236 | 3.3 | 156.2 | 58.28 | 47.33 | 0.615 |
| 2908 | 17.48 | 92.00 | 3.461 | 2.3 | 168.8 | 58.62 | 73.39 | 0.606 |

TABLE D-19 (DISPLACEMENT DATA)

RUN-219

WAINWRIGHT(1080)CS

Q= 600.0 CC/HR

SWI= 7.13 PER CENT

K= 11.43 DARCY

TEMP= 22.2 C

KOI= 8.03 DARCY

IOIP= 692.1 CC

PORE VOL.= 745.2 CC

| DATE | TIME (HRS) | PRESS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|-------------------------|--------|--------------|
| 909 | 8.15 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.071 |
| 909 | 8.23 | 1250.00 | 0.080 | 30.8 | 0.0 | 3.03 | 0.00 | 0.151 |
| 909 | 8.26 | 1340.00 | 0.123 | 30.8 | 0.0 | 7.48 | 0.00 | 0.194 |
| 909 | 8.29 | 1230.00 | 0.161 | 30.8 | 0.0 | 11.93 | 0.00 | 0.232 |
| 909 | 8.32 | 940.00 | 0.201 | 29.7 | 0.1 | 16.22 | 0.00 | 0.272 |
| 909 | 8.35 | 505.00 | 0.249 | 31.9 | 12.9 | 20.83 | 0.40 | 0.303 |
| 909 | 8.41 | 375.00 | 0.328 | 24.7 | 40.4 | 24.40 | 1.63 | 0.328 |
| 909 | 8.47 | 307.00 | 0.409 | 18.0 | 43.9 | 27.00 | 2.43 | 0.349 |
| 909 | 8.56 | 225.00 | 0.536 | 32.3 | 66.5 | 31.67 | 2.05 | 0.388 |
| 909 | 9.06 | 165.00 | 0.670 | 17.0 | 83.5 | 34.12 | 4.91 | 0.410 |
| 909 | 9.16 | 122.00 | 0.805 | 12.1 | 94.9 | 35.87 | 7.84 | 0.417 |
| 909 | 9.25 | 102.00 | 0.925 | 9.5 | 88.5 | 37.24 | 9.31 | 0.419 |
| 909 | 9.41 | 90.00 | 1.153 | 8.6 | 162.7 | 38.49 | 18.91 | 0.429 |
| 909 | 10.01 | 85.00 | 1.356 | 7.4 | 151.3 | 39.56 | 20.44 | 0.428 |
| 909 | 10.15 | 81.00 | 1.552 | 4.6 | 144.1 | 40.22 | 31.32 | 0.431 |
| 909 | 10.31 | 77.00 | 1.759 | 5.3 | 153.7 | 40.99 | 29.00 | 0.431 |
| 909 | 10.46 | 74.00 | 1.973 | 4.0 | 156.8 | 41.56 | 39.20 | 0.435 |
| 909 | 11.02 | 72.00 | 2.193 | 8.6 | 162.7 | 42.81 | 18.91 | 0.437 |
| 909 | 11.17 | 69.00 | 2.405 | 3.3 | 160.4 | 43.28 | 48.60 | 0.434 |
| 909 | 11.33 | 67.00 | 2.625 | 3.2 | 165.9 | 43.75 | 51.84 | 0.431 |
| 909 | 11.54 | 65.00 | 2.847 | 2.4 | 164.3 | 44.09 | 68.45 | 0.432 |
| 909 | 12.10 | 62.00 | 3.086 | 1.3 | 177.9 | 44.28 | 136.84 | 0.432 |
| 909 | 12.27 | 60.00 | 3.314 | 1.2 | 169.4 | 44.45 | 141.16 | 0.433 |
| 909 | 12.41 | 59.00 | 3.515 | 1.5 | 148.1 | 44.67 | 98.73 | 0.436 |

TABLE D-20 (DISPLACEMENT DATA)

RUN-220

WAINWRIGHT(1080)CS

Q= 800.0 CC/HR

SWI= 7.18 PER CENT

K= 12.52 DARCY

TEMP= 20.5 C

KOI= 9.36 DARCY

IOIP= 711.2 CC

PORE VOL.= 766.2 CC

| DATE | TIME (HRS) | PR FSS DRDP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|-------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 1909 | 8.25 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.071 |
| 1909 | 8.30 | 1620.00 | 0.079 | 30.4 | 0.0 | 2.89 | 0.00 | 0.151 |
| 1909 | 8.32 | 1800.00 | 0.125 | 30.2 | 0.0 | 7.14 | 0.00 | 0.197 |
| 1909 | 8.35 | 1750.00 | 0.164 | 30.7 | 0.0 | 11.45 | 0.00 | 0.236 |
| 1909 | 8.37 | 1600.00 | 0.198 | 30.4 | 0.0 | 15.73 | 0.00 | 0.270 |
| 1909 | 8.39 | 1425.00 | 0.234 | 31.0 | 0.0 | 20.09 | 0.00 | 0.306 |
| 1909 | 8.40 | 1310.00 | 0.255 | 19.5 | 0.0 | 22.83 | 0.00 | 0.327 |
| 1909 | 8.42 | 880.00 | 0.284 | 28.0 | 1.5 | 26.77 | 0.05 | 0.354 |
| 1909 | 8.44 | 510.00 | 0.336 | 30.8 | 1.5 | 31.10 | 0.04 | 0.404 |
| 1909 | 8.47 | 475.00 | 0.378 | 22.7 | 12.5 | 34.29 | 0.55 | 0.430 |
| 1909 | 8.49 | 407.00 | 0.422 | 15.7 | 21.0 | 36.50 | 1.33 | 0.447 |
| 1909 | 9.01 | 255.00 | 0.626 | 23.5 | 138.5 | 39.80 | 5.89 | 0.469 |
| 1909 | 9.14 | 160.00 | 0.866 | 27.2 | 160.5 | 43.63 | 5.90 | 0.500 |
| 1909 | 9.28 | 125.00 | 1.119 | 9.7 | 174.0 | 44.99 | 17.93 | 0.526 |
| 1909 | 9.38 | 122.00 | 1.297 | 4.5 | 138.5 | 45.62 | 30.77 | 0.523 |
| 1909 | 10.33 | 120.00 | 1.527 | 8.0 | 168.0 | 46.75 | 21.00 | 0.533 |
| 1909 | 10.45 | 113.00 | 1.735 | 4.4 | 158.6 | 47.37 | 36.04 | 0.535 |
| 1909 | 10.56 | 107.00 | 1.934 | 3.0 | 153.9 | 47.79 | 51.30 | 0.533 |
| 1909 | 11.08 | 103.00 | 2.140 | 3.2 | 157.6 | 48.24 | 49.25 | 0.533 |
| 1909 | 11.20 | 98.00 | 2.357 | 2.9 | 165.3 | 48.65 | 57.00 | 0.534 |
| 1909 | 11.32 | 95.00 | 2.560 | 2.0 | 154.0 | 48.93 | 77.00 | 0.537 |

TABLE D-21 (DISPLACEMENT DATA)

RUN-221

WAINWRIGHT(1080)CS

Q= 800.0 CC/HR

SWI= 5.40 PER CENT

K= 15.09 DARCY

TEMP= 21.1 C

KOI= 13.24 DARCY

IOIP= 741.3 CC

PORE VOL.= 794.6 CC

| DATE | TIME (HRS) | PR FSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|-------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 1709 | 10.40 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.054 |
| 1709 | 10.44 | 1307.00 | 0.075 | 35.3 | 0.0 | 3.38 | 0.00 | 0.129 |
| 1709 | 10.47 | 1340.00 | 0.113 | 30.2 | 0.0 | 7.45 | 0.00 | 0.167 |
| 1709 | 10.49 | 1245.00 | 0.151 | 31.7 | 0.0 | 11.73 | 0.00 | 0.205 |
| 1709 | 10.51 | 1110.00 | 0.188 | 31.6 | 0.0 | 15.99 | 0.00 | 0.242 |
| 1709 | 10.55 | 827.00 | 0.259 | 63.8 | 0.0 | 24.60 | 0.00 | 0.313 |
| 1709 | 11.00 | 510.00 | 0.337 | 64.7 | 0.3 | 33.33 | 0.00 | 0.390 |
| 1709 | 11.03 | 350.00 | 0.382 | 14.1 | 22.5 | 35.23 | 1.59 | 0.407 |
| 1709 | 11.10 | 284.00 | 0.503 | 24.8 | 77.2 | 38.58 | 3.11 | 0.431 |
| 1709 | 11.20 | 188.00 | 0.692 | 18.8 | 133.4 | 41.11 | 7.09 | 0.452 |
| 1709 | 11.30 | 150.00 | 0.843 | 7.7 | 112.4 | 42.15 | 14.59 | 0.461 |
| 1709 | 11.40 | 125.00 | 1.016 | 3.8 | 142.0 | 42.66 | 37.36 | 0.456 |
| 1709 | 11.50 | 108.00 | 1.220 | 4.7 | 159.9 | 43.30 | 34.02 | 0.459 |
| 1709 | 12.04 | 105.00 | 1.430 | 3.8 | 166.6 | 43.81 | 43.84 | 0.460 |
| 1709 | 12.15 | 97.00 | 1.619 | 2.9 | 155.0 | 44.20 | 53.44 | 0.453 |
| 1709 | 12.26 | 93.00 | 1.820 | 2.1 | 158.5 | 44.48 | 75.47 | 0.455 |
| 1709 | 12.39 | 88.00 | 2.029 | 2.0 | 163.5 | 44.75 | 81.75 | 0.458 |

TABLE D-22 (DISPLACEMENT DATA)

RUN-401

DC200(500)CS

Q= 10.0 CC/HR

SWI=10.20 PER CENT

K= 16.46 DARCY

TEMP= 22.0 C

KOI= 15.00 DARCY

IOIP=2666.9 CC

PORE VOL.=2969.5 CC

| DATE | TIME (HRS) | PRFSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|--------------------------|-------|--------------|
| 501 | 16.45 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.102 |
| 501 | 19.55 | 2.11 | 0.010 | 28.5 | 0.0 | 0.07 | 0.00 | 0.112 |
| 601 | 10.40 | 1.36 | 0.062 | 152.7 | 0.0 | 5.80 | 0.00 | 0.164 |
| 601 | 14.25 | 1.24 | 0.074 | 40.0 | 0.0 | 7.30 | 0.00 | 0.176 |
| 601 | 22.10 | 1.04 | 0.101 | 81.4 | 0.0 | 10.35 | 0.00 | 0.203 |
| 701 | 13.25 | 0.99 | 0.153 | 152.5 | 0.8 | 16.07 | 0.00 | 0.255 |
| 701 | 14.50 | 0.98 | 0.158 | 14.1 | 7.9 | 16.60 | 0.56 | 0.258 |
| 701 | 20.00 | 0.90 | 0.176 | 28.9 | 22.9 | 17.68 | 0.79 | 0.268 |
| 701 | 22.00 | 0.90 | 0.183 | 13.5 | 9.0 | 18.19 | 0.66 | 0.271 |
| 801 | 11.30 | 0.76 | 0.230 | 71.0 | 72.2 | 20.85 | 1.01 | 0.294 |
| 801 | 21.05 | 0.65 | 0.249 | 19.7 | 39.1 | 21.59 | 1.98 | 0.300 |
| 901 | 9.30 | 0.61 | 0.292 | 39.7 | 92.3 | 23.08 | 2.32 | 0.312 |
| 901 | 19.55 | 0.56 | 0.328 | 25.3 | 81.3 | 24.02 | 3.21 | 0.320 |
| 1001 | 23.50 | 0.47 | 0.424 | 53.3 | 241.6 | 26.02 | 4.53 | 0.336 |
| 1101 | 10.10 | 0.45 | 0.460 | 18.1 | 92.8 | 26.70 | 5.12 | 0.340 |
| 1201 | 10.00 | 0.41 | 0.530 | 27.3 | 187.3 | 27.73 | 6.86 | 0.347 |
| 1201 | 20.00 | 0.40 | 0.564 | 12.3 | 91.0 | 28.19 | 7.39 | 0.350 |
| 1401 | 8.50 | 0.41 | 0.643 | 27.0 | 214.0 | 29.20 | 7.92 | 0.357 |
| 1401 | 21.15 | 0.39 | 0.686 | 10.9 | 120.5 | 29.61 | 11.05 | 0.360 |
| 1501 | 10.10 | 0.40 | 0.731 | 12.2 | 125.1 | 30.07 | 10.25 | 0.362 |
| 1501 | 21.00 | 0.39 | 0.770 | 8.6 | 107.7 | 30.39 | 12.52 | 0.365 |
| 1601 | 10.40 | 0.38 | 0.817 | 7.9 | 130.1 | 30.68 | 16.46 | 0.368 |
| 1601 | 23.20 | 0.38 | 0.861 | 7.9 | 125.6 | 30.98 | 15.89 | 0.369 |
| 1701 | 21.30 | 0.38 | 0.937 | 12.7 | 215.5 | 31.46 | 16.96 | 0.373 |
| 1801 | 15.00 | 0.38 | 0.984 | 9.0 | 129.0 | 31.79 | 14.33 | 0.377 |
| 1901 | 11.00 | 0.39 | 1.062 | 7.8 | 197.0 | 32.09 | 25.25 | 0.389 |
| 2001 | 9.20 | 0.35 | 1.136 | 12.3 | 209.2 | 32.55 | 17.00 | 0.392 |
| 2001 | 19.00 | 0.33 | 1.169 | 4.8 | 97.2 | 32.73 | 20.25 | 0.392 |
| 2101 | 19.00 | 0.35 | 1.250 | 10.5 | 231.0 | 33.12 | 22.00 | 0.396 |
| 2201 | 17.30 | 0.35 | 1.328 | 9.0 | 219.0 | 33.46 | 24.33 | 0.400 |
| 2401 | 16.00 | 0.35 | 1.480 | 13.0 | 439.0 | 33.95 | 33.76 | 0.404 |
| 2501 | 16.00 | 0.34 | 1.563 | 7.0 | 236.0 | 34.21 | 33.71 | 0.408 |
| 2601 | 15.30 | 0.34 | 1.644 | 7.5 | 228.0 | 34.49 | 30.40 | 0.412 |
| 2701 | 16.35 | 0.33 | 1.731 | 8.0 | 250.0 | 34.79 | 31.25 | 0.415 |

TABLE D-23 (DISPLACEMENT DATA)

RUN-402

DC200(500)CS

K = 18.28 DARCY

Q= 40.0 CC/HR

SWI=10.80 PER CENT

TEMP= 22.0 C

KOI= 15.73 DARCY

IOIP=2631.6 CC

PORE VOL.=2961.4 CC

| DATE | TIME (HRS) | PRFSS DROP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (% IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|--------------------------|-------|--------------|
| 1305 | 15.50 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.108 |
| 1305 | 16.50 | 7.65 | 0.013 | 37.0 | 0.0 | 0.09 | 0.00 | 0.121 |
| 1305 | 19.30 | 6.45 | 0.050 | 108.0 | 0.0 | 4.19 | 0.00 | 0.158 |
| 1305 | 20.50 | 6.11 | 0.069 | 50.0 | 0.0 | 6.09 | 0.00 | 0.177 |
| 1305 | 21.45 | 5.86 | 0.081 | 36.5 | 0.0 | 7.48 | 0.00 | 0.189 |
| 1405 | 11.00 | 1.62 | 0.237 | 464.0 | 0.0 | 25.11 | 0.00 | 0.345 |
| 1405 | 12.00 | 1.56 | 0.249 | 18.7 | 15.9 | 25.82 | 0.85 | 0.352 |
| 1405 | 16.30 | 1.29 | 0.312 | 45.7 | 141.0 | 27.56 | 3.08 | 0.367 |
| 1405 | 23.20 | 1.10 | 0.393 | 34.5 | 206.0 | 28.87 | 5.97 | 0.379 |
| 1505 | 11.30 | 0.83 | 0.569 | 57.0 | 467.2 | 31.04 | 8.19 | 0.397 |
| 1505 | 16.15 | 0.75 | 0.636 | 17.6 | 180.5 | 31.71 | 10.25 | 0.403 |
| 1505 | 22.00 | 0.71 | 0.716 | 18.5 | 218.5 | 32.41 | 11.81 | 0.409 |
| 1605 | 10.30 | 0.65 | 0.884 | 30.0 | 465.2 | 33.55 | 15.50 | 0.420 |
| 1605 | 16.00 | 0.62 | 0.962 | 9.5 | 220.5 | 33.91 | 23.21 | 0.423 |
| 1605 | 21.00 | 0.51 | 1.029 | 8.0 | 191.0 | 34.21 | 23.87 | 0.426 |
| 1705 | 9.25 | 0.49 | 1.197 | 21.6 | 478.6 | 35.03 | 22.15 | 0.432 |
| 1705 | 15.30 | 0.46 | 1.280 | 12.0 | 235.0 | 35.49 | 19.58 | 0.436 |
| 1705 | 21.30 | 0.41 | 1.364 | 7.5 | 238.0 | 35.77 | 31.73 | 0.440 |
| 1805 | 10.00 | 0.40 | 1.532 | 13.8 | 481.9 | 36.30 | 34.92 | 0.445 |
| 1805 | 15.50 | 0.38 | 1.613 | 8.5 | 231.0 | 36.62 | 27.17 | 0.448 |
| 1805 | 20.30 | 0.37 | 1.678 | 3.2 | 190.0 | 36.74 | 59.37 | 0.449 |
| 1905 | 8.45 | 0.37 | 1.846 | 13.7 | 486.7 | 37.26 | 35.52 | 0.453 |
| 1905 | 15.30 | 0.36 | 1.938 | 8.0 | 263.0 | 37.57 | 32.87 | 0.455 |
| 1905 | 21.15 | 0.34 | 2.014 | 9.0 | 221.0 | 37.91 | 24.55 | 0.457 |
| 2005 | 9.30 | 0.34 | 2.178 | 11.4 | 471.9 | 38.34 | 41.39 | 0.462 |
| 2005 | 15.30 | 0.34 | 2.260 | 4.0 | 244.0 | 38.50 | 61.00 | 0.461 |
| 2005 | 21.30 | 0.33 | 2.341 | 3.0 | 23.6 | 38.61 | 7.88 | 0.535 |
| 2105 | 9.30 | 0.31 | 2.509 | 11.0 | 480.0 | 39.03 | 43.63 | 0.540 |
| 2105 | 15.00 | 0.31 | 2.583 | 5.5 | 215.5 | 39.24 | 39.18 | 0.542 |
| 2105 | 21.30 | 0.31 | 2.676 | 60.0 | 263.0 | 41.52 | 4.38 | 0.545 |
| 2205 | 9.00 | 0.31 | 2.845 | 12.5 | 489.5 | 41.99 | 39.16 | 0.549 |

TABLE D-24 (DISPLACEMENT DATA)

RUN-403

DC200(500)CS

K= 11.33 DARCY

Q= 600.0 CC/HR

SWI=11.73 PER CENT

TEMP= 21.0 C

KNT= 10.09 DARCY

IOIP=2654.8 CC

PORF VOL.=3007.5 CC

| DATE | TIME (HRS) | PRESS DROP (PSI) | TOTAL INJ (PV) | OIL PRND (CC) | WATER PRND (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 1906 | 14.40 | 0.00 | 0.0000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.117 |
| 1906 | 14.44 | 164.20 | 0.014 | 42.5 | 0.5 | 0.30 | 0.01 | 0.131 |
| 1906 | 14.50 | 153.40 | 0.033 | 54.9 | 0.5 | 2.36 | 0.00 | 0.150 |
| 1906 | 15.00 | 134.30 | 0.068 | 94.0 | 0.7 | 5.90 | 0.00 | 0.185 |
| 1906 | 15.10 | 112.30 | 0.103 | 99.1 | 0.6 | 9.64 | 0.00 | 0.219 |
| 1906 | 15.20 | 86.00 | 0.135 | 97.0 | 0.7 | 13.29 | 0.00 | 0.251 |
| 1906 | 15.25 | 75.00 | 0.149 | 42.0 | 1.0 | 14.87 | 0.02 | 0.265 |
| 1906 | 15.36 | 54.60 | 0.190 | 81.9 | 35.1 | 17.96 | 0.42 | 0.294 |
| 1906 | 15.53 | 40.80 | 0.250 | 86.1 | 96.8 | 21.20 | 1.12 | 0.322 |
| 1906 | 16.12 | 32.40 | 0.309 | 59.4 | 123.4 | 23.44 | 2.07 | 0.340 |
| 1906 | 16.34 | 29.80 | 0.371 | 44.8 | 142.0 | 25.13 | 3.16 | 0.355 |
| 1906 | 16.52 | 24.00 | 0.434 | 37.8 | 157.0 | 26.55 | 4.15 | 0.366 |
| 1906 | 17.12 | 21.00 | 0.498 | 32.7 | 159.8 | 27.78 | 4.88 | 0.377 |
| 1906 | 17.35 | 18.40 | 0.581 | 30.0 | 218.0 | 28.91 | 7.26 | 0.387 |
| 1906 | 17.53 | 16.90 | 0.641 | 22.4 | 161.5 | 29.76 | 7.20 | 0.393 |
| 1906 | 18.36 | 14.60 | 0.770 | 39.0 | 352.0 | 31.22 | 9.02 | 0.405 |
| 1906 | 19.12 | 13.00 | 0.897 | 33.2 | 348.4 | 32.48 | 10.49 | 0.416 |
| 1906 | 19.53 | 11.60 | 1.021 | 38.5 | 345.1 | 33.93 | 8.96 | 0.426 |
| 1906 | 20.11 | 11.40 | 1.082 | 10.0 | 172.5 | 34.30 | 17.25 | 0.429 |
| 1906 | 20.29 | 11.00 | 1.140 | 11.2 | 173.8 | 34.72 | 15.51 | 0.430 |
| 1906 | 20.47 | 10.40 | 1.204 | 10.5 | 174.6 | 35.12 | 16.62 | 0.436 |
| 1906 | 21.24 | 9.70 | 1.326 | 20.5 | 356.7 | 35.89 | 17.39 | 0.439 |
| 1906 | 21.49 | 9.30 | 1.393 | 10.0 | 188.5 | 36.27 | 18.85 | 0.443 |
| 1906 | 22.31 | 8.90 | 1.536 | 17.8 | 413.2 | 36.94 | 23.21 | 0.448 |
| 1906 | 22.49 | 8.60 | 1.596 | 6.4 | 177.9 | 37.18 | 27.79 | 0.450 |
| 1906 | 23.31 | 8.00 | 1.721 | 17.4 | 357.0 | 37.84 | 20.51 | 0.456 |
| 1906 | 23.50 | 8.00 | 1.785 | 6.8 | 187.8 | 38.09 | 27.61 | 0.457 |
| 2006 | 0.27 | 7.60 | 1.910 | 13.2 | 364.6 | 38.59 | 27.62 | 0.461 |
| 2006 | 0.50 | 7.50 | 1.989 | 7.0 | 237.9 | 38.85 | 33.98 | 0.461 |
| 2006 | 2.11 | 7.00 | 2.117 | 13.7 | 365.0 | 39.37 | 26.64 | 0.468 |
| 2006 | 2.30 | 6.80 | 2.182 | 5.3 | 191.7 | 39.57 | 36.16 | 0.469 |
| 2006 | 3.18 | 6.50 | 2.327 | 13.4 | 421.7 | 40.07 | 31.47 | 0.474 |
| 2006 | 3.55 | 6.40 | 2.451 | 10.7 | 367.5 | 40.48 | 34.34 | 0.476 |
| 2006 | 4.29 | 6.20 | 2.576 | 7.5 | 367.8 | 40.76 | 49.04 | 0.478 |
| 2006 | 5.15 | 5.90 | 2.716 | 11.6 | 416.6 | 41.20 | 35.91 | 0.480 |
| 2006 | 5.58 | 5.80 | 2.845 | 11.2 | 376.3 | 41.62 | 33.59 | 0.484 |

TABLE D-25 (DISPLACEMENT DATA)

RUN-404

DC 200 (500) CS

K= 10.39 DARCY

Q=1120.0 CC/HR

SWI=10.34 PER CENT

TEMP= 22.0 C

KOI= 9.89 DARCY

IOIP=2589.9 CC

PORE VOL.=2888.6 CC

| DATE | TIME (HRS) | PRF SS DRIP (PSI) | TOTAL INJ (PV) | OIL PROD (CC) | WATER PROD (CC) | TOTAL OIL (%IOIP) | WOR | AVE. SAT. |
|------|---------------|-------------------------|----------------------|---------------------|-----------------------|-------------------------|-------|--------------|
| 2507 | 2.11 | 0.00 | 0.000 | 0.0 | 0.0 | 0.00 | 0.00 | 0.103 |
| 2507 | 2.22 | 298.00 | 0.055 | 135.2 | 0.5 | 3.88 | 0.00 | 0.158 |
| 2507 | 2.25 | 277.00 | 0.075 | 49.6 | 0.6 | 5.80 | 0.01 | 0.178 |
| 2507 | 2.37 | 156.00 | 0.155 | 231.9 | 2.3 | 14.75 | 0.01 | 0.257 |
| 2507 | 2.47 | 103.00 | 0.215 | 116.6 | 70.5 | 19.26 | 0.60 | 0.293 |
| 2507 | 2.58 | 80.80 | 0.281 | 72.8 | 118.8 | 22.07 | 1.63 | 0.318 |
| 2507 | 3.11 | 65.00 | 0.347 | 55.0 | 147.0 | 24.19 | 2.67 | 0.333 |
| 2507 | 3.32 | 47.60 | 0.478 | 86.1 | 290.5 | 27.52 | 3.37 | 0.363 |
| 2507 | 3.52 | 35.50 | 0.609 | 57.0 | 324.0 | 29.72 | 5.68 | 0.382 |
| 2507 | 4.06 | 31.00 | 0.694 | 30.0 | 227.8 | 30.87 | 7.59 | 0.389 |
| 2507 | 5.05 | 26.70 | 0.824 | 33.3 | 342.4 | 32.16 | 10.28 | 0.400 |
| 2507 | 5.25 | 24.60 | 0.949 | 30.6 | 339.5 | 33.34 | 11.09 | 0.407 |
| 2507 | 5.39 | 22.60 | 1.042 | 18.9 | 262.5 | 34.07 | 13.88 | 0.409 |
| 2507 | 6.27 | 20.80 | 1.139 | 21.0 | 349.3 | 34.88 | 16.63 | 0.385 |
| 2507 | 6.47 | 19.60 | 1.268 | 19.0 | 360.3 | 35.62 | 18.96 | 0.389 |
| 2507 | 7.00 | 18.60 | 1.355 | 13.7 | 264.5 | 36.15 | 19.30 | 0.385 |
| 2507 | 7.25 | 17.60 | 1.482 | 20.7 | 347.6 | 36.94 | 16.79 | 0.392 |
| 2507 | 7.46 | 16.40 | 1.612 | 13.8 | 375.2 | 37.48 | 27.18 | 0.392 |
| 2507 | 8.00 | 15.80 | 1.703 | 7.0 | 265.5 | 37.75 | 37.92 | 0.390 |

B30210